

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-083-20639-0000

LEASE NAME Hays

WELL NUMBER A-4

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

 Ft. from S Section Line

 Ft. from E Section Line
W/2 NW SE

SEC. 19 TWP. 22S RGE. 23W (E) or (W)

COUNTY Hodgeman

LEASE OPERATOR Edmiston Oil Company, Inc.

1260 KSB Bldg.

ADDRESS Wichita, Kansas 67202

PHONE# (316) 265-5241 OPERATORS LICENSE NO. 5042

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed

Plugging Commenced 2-3-87

Plugging Completed 2-10-87

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dodge City, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4709'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	370'	none
				4-1/2"	4708'	3050'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 4625' and 4 sacks cement. Shot pipe @3050'. pulled a total of 74 joints of 4-1/2" casing. Plugged surface with 2 hulls, 15 gel, 50 cement, 20 gel, 1 hull, 150 cement, 60/40 pos, 6% gel.
Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso, President

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 18th day of February, 19 87

Jane Hoover
Notary Public

My Commission Expires:



STATE CORPORATION COMMISSION

2-19-87
FEB 19 1987 Form CP-4
Revised 07-86
CONSERVATION DIVISION
Wichita, Kansas