

RECEIVED

MAR 04 2002

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-055-20071-00-00

LEASE NAME Stevenson

WELL NUMBER 1

4620 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 6 TWP. 22S RGE. 33 (E) or (W)

COUNTY Finney

Date Well Completed 3-21-72

Plugging Commenced 2-18-02

Plugging Completed 2-20-02

3-7-02
RECEIVED
MAR 07 2002
KCC WICHITA

LEASE OPERATOR GMX Resources, Inc.

ADDRESS 9400 N. Broadway, Ste. 600, Oklahoma City

PHONE#(405) 600-0711 OPERATORS LICENSE NO. 32281 OK 73114

Character of Well P&A

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on Steve Pfeifer (date)
by 2-18-02 (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Mississippian Depth to Top 4719 Bottom 4724 T.D. 4780

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippian		0	401	8-5/8	401	0
		4779		5-1/2	4779	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Set CIBP at 1150', perforate 4 squeeze holes at 1100', pump 180 sacks 60/40 poz, 6% gel down casing, displace 80 sacks cement outside casing and leave casing full of cement, dump 150 sacks 60/40 poz, 6% gel down 5-1/2" x 8-5/8" annulus.

Name of Plugging Contractor Allied Cementing License No. _____

Address PO Box 31, Russell, KS 67665-0031

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: GMX Resources, Inc.

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

William A. Buntyn (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) William A. Buntyn

(Address) 9400 N. Broadway, Suite 600, Oklahoma City, OK 73114

SUBSCRIBED AND SWORN TO before me this 4th day of March, 19 2002

Mary Alice Falk
Notary Public

My Commission Expires: December 14, 2004

OK