

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Hodgeman County. Sec. 8 Twp. 22 Rge. 23 (E) (W) X

Location as "NE/CNW/SW" or footage from lines. C- NE - SW

Lease Owner Colorado Oil & Gas Corporation

Lease Name Bradley Well No. 1

Office Address 1020 Hoover Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_

Date well completed \_\_\_\_\_ 19\_\_

Application for plugging filed \_\_\_\_\_ 19\_\_

Application for plugging approved \_\_\_\_\_ 19\_\_

Plugging commenced 12-21-65 \_\_\_\_\_ 19\_\_

Plugging completed 1-3-66 \_\_\_\_\_ 19\_\_

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Hugh E. Scott

Name of Conservation Agent who supervised plugging of this well

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well PB 4687 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	407	None
				5 1/2	None	2474

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pumped 20 sacks of cement to 4600'. Cleaned out cellar. Rigged up. Cut out dutchman. Pulled off collar.

Welded on collar. Working pipe. Shot pipe at 3850' - 3762'.

Circulating. Spotted 80 hbl. of oil.

Working pipe. Shot pipe at 3500' - 3000' - 2800' - 2600' & 2500'. Pulling pipe.

Pulling pipe. Plugging well. Pumped in 35 sacks of cement at 450'. Capped well with 15 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 12 1966

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.  
Address P. O. Box 221 Great Bend, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF Kansas COUNTY OF Barton, ss.  
J. O. Forbes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

J. O. Forbes  
P. O. Box 221 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 11 day of January, 19 66

My commission expires May 27, 1969

Notary Public.

# WELL LOG

15.083-10047-0000

COMPANY COLORADO OIL & GAS COMPANY

SEC. 8 T28 R. 23W

FARM BRADLEY NO. 1


LOC. C-NE, SW.

TOTAL DEPTH 4720'

COUNTY HODGEMAN CO., KANSAS

COMM. May 11, 1960 COMP. May 26, 1960

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 407' w/250 sax.  
5 1/2" @ 4717' w/100 sax.

ELEVATION 2407' DF

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

217	Surface soil & shale
409	Shale & shells
610	Shale
1050	Red bed
1100	Anhydrite
1520	Shale & sand
1600	Sand & shale
2100	Shale & lime
2400	Shale
2515	Shale & lime
2630	Lime & shale
2785	Lime
2815	Lime & shale
3115	Lime
3635	Lime & shale
3700	Lime
3805	Lime & chalk
3875	Chalky lime
4025	Chalky lime & shale
4470	Lime
4650	Lime & shale
4706	Lime & chert
4720	Lime
4720	T. D.

RECEIVED  
STATE CORPORATION COMMISSION

DEC -2 1965

CONSERVATION DIVISION  
Wichita, Kansas

State of KANSAS  
County of BARTON } ss.

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 BRADLEY well

Subscribed and sworn to before me this 3rd day of June 19 60

My Commission Expires: November 12, 1962

*Verne A. Morris*  
*[Signature]*  
NOTARY PUBLIC

001-17001-11 941

Colorado Oil & Gas Co.  
Production Department

JUN 14 1960

Liberel, Kansas