


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Hodgeman County, Sec. 8 Twp. 22S Rge. 23W E/W  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines  
NE SE SW

Lease Owner American Energies Corporation  
Lease Name Selfridge Well No. 1  
Office Address 575 Fourth Financial Center, Wichita, KS  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above Section Plat

Date Well completed December 14 1980  
Application for plugging filed December 14 1980  
Application for plugging approved December 14 1980  
Plugging commenced December 14 1980  
Plugging completed December 14 1980  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt  
Producing formation Depth to top Bottom Total Depth of Well 4701  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
surface hole	shale	surface	320	8-5/8	317	none
	Cemented with	250 sx	common,	2% gel,	3% cc,	plug
	down @ 5:15	p.m. 12-7-80	By Sun.	cement	did circ.	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged as follows:

Plugged w/50-50 posmix, 6% gel

60 sx @ 900'

30 sx @ 300'

10 sx & bridge plug @ 40'

5 sx in rat hole

Job completed @ 3:30 p.m. 12-14-80 by Sun;

State Pluggger; Marion Schmidt

12-18-80

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Husky Drilling Co., Inc.

DEC 18 1980

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
Jon T. Williams, Jr. (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature)

200 E. First, Suite 500, Wichita, KS 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of December, 1980

Geraldine Stewart  
Geraldine Stewart Notary Public.

My commission expires January 12, 1981





200 East First, Suite 500  
~~800 Bittling Bldg~~  
 Wichita, Kansas 67202  
 Phone 316 - 263-7904  
 Mobile Phone 316 - 793-7859 Unit 7070

December 16, 1980

WELL LOG-----Selfridge No. 1  
 Located: NE SE SW of Sec. 8-22S-23W, Hodgeman Co., Kansas

OWNER: American Energies Corporation  
 ROTARY CONTRACTOR: Husky Drilling Company, Inc.

COMMENCED: December 6, 1980  
 COMPLETED: December 14, 1980

Rotary Total Depth: 4701'

LOG

0 - 130	Surface soil, shale & post rock
130 - 320	Soil & sand
320 - 820	Sahle & sand streaks
820 - 1147	Red Bed & shale
1147 - 1340	Sand
1340 - 1669	Shale & sand
1669 - 1703	Anhydrite
1703 - 1756	Shale & shells
1756 - 4225	Shale & lime
4225 - 4500	Lime
4500 - 4671	Lime & shale
4671 - 4695	Chert
4695 - 4701	Lime

CASING RECORD

Ran 7 jts., used 24#, 8-5/8" casing,  
 tallied 310.69' set @ 317 KB w/250 sx,  
 common 2% gel, 3% cc, plug down @  
 3:15 p.m. by Sun; cement did circ.

Plugged &amp; Abandoned 12-14-80.

I certify the above to be a true and correct copy of the driller's  
 log to the best of my knowledge and belief.

HUSKY DRILLING CO., INC.

By

Jon T. Williams, Jr., President

RECEIVED  
 CONSERVATION COMMISSION

DEC 18 1980

CONSERVATION DIVISION  
 Wichita, Kansas