


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Hodgeman County, Sec 6 Twp. 22 Rge. (E) 23 (W)
Location as "NE/CNW/SW" or footage from lines NW SW
Lease Owner Petroleum, Inc.
Lease Name Goebel "H" Well No. 1
Office Address R. H. Garvey Bldg., 300 West Douglas, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole 67202
Date well completed February 10 19 74
Application for plugging filed February 10 19 74
Application for plugging approved February 10 19 74
Plugging commenced February 10 19 74
Plugging completed February 10 19 74
Reason for abandonment of well or producing formation Dry Hole
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves, Sublette
Producing formation Depth to top Bottom Total Depth of Well 4700 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	404.40'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.


Hole plugged as follows: Plugged at 900' with 70 sacks of common cement and 2% gel; plugged at 380' with 25 sacks of common cement and 2% gel; plugged at 40' with 10 sacks of common cement and 2% gel. Plug down at 7:00 P. M. February 10, 1974.

RECEIVED
STATE CORPORATION COMMISSION
FEB 15 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Strata Drilling, Inc.
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Charles W. Steincamp (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp
Charles W. Steincamp, President
P. O. Box 355, Great Bend, Kansas 67530
(Address)



Subscribed and Sworn to before me this 12th day of February, 1974.
December 14, 1977
Elaine H. Taylor Notary Public.

D R I L L E R S L O G

#1 Goebel "H"

CASING RECORD:
399.40' of new 8-5/8"
surface casing.

COMPANY: Petroleum, Inc.
CONTRACTOR: Strata Drilling, Inc.

DESCRIPTION: NW SW
Section 6-22S-23W
Hodgeman County, Kansas

TOTAL DEPTH:
4700'

COMMENCED: January 31, 1974
COMPLETED: February 10, 1974

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale, Post Rock & Shells	0	250	Ran 399.40' of new 8-5/8" surface casing; set and cemented at 404.40' with 250 sacks of common cement, 2% gel and 3% C. C. Plug down at 8:00 A. M. February 1, 1974.
Sand, Clay & Shells	250	420	
Shale, Sand & Shells	420	1040	
Sand, Shale & Red Bed	1040	1681	
Shale & Lime	1681	2760	
Lime	2760	2970	
Lime & Shale	2970	4600	
Lime	4600	4700	

ROTARY TOTAL DEPTH: 4700'

Ran electric log.

D. & A.

RECEIVED
STATE CORPORATION COMMISSION

FEB 15 1974

CONSERVATION DIVISION
Wichita, Kansas

Plugged hole as follows: Plugged at 900' with 70 sacks of common cement and 2% gel; plugged at 380' with 25 sacks of common cement and 2% gel; plugged at 40' with 10 sacks of common cement and 2% gel. Plug down at 7:00 P. M. February 10, 1974.

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp
Charles W. Steincamp, President

Subscribed and sworn to before me this 12th day of February, 1974.

My Commission Expires:

December 14, 1977

Elaine H. Taylor
Elaine H. Taylor, Notary Public

