

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Hodgeman County, Sec. 20 Twp. 22 Rge. (E) 22 (W)

Location as "NE/CNW%SW%" or footage from lines SW NE

Lease Owner Sun Oil Company

Lease Name Bamberger Well No. 7

Office Address 800 Security Life Bldg.

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 2-16 19 63

Application for plugging filed 12-12 19 73

Application for plugging approved 12-14 19 73

Plugging commenced 8-25 19 74

Plugging completed 9-5 19 74

Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar Eves

Producing formation Marm. Cher. Depth to top 4252 Bottom 4434 Total Depth of Well 4491 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE  | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
|           |         |      |    | 9 5/8 | 251    | -          |
|           |         |      |    | 5 1/2 | 4484   | 3488       |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set plug at 4240. Dumped 4 sx cement with dump bailer.  
Shot pipe at 3488. Pulled and layed down 3488' of 5 1/2" casing.  
Plugged with 80 sx of cement, 14 sx gel, 30 sx cement, 8 sx gel, and 10 sx cement,  
Plug at surface.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 30 1974

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Charlie Crow Drilling Co.

Address Box 706, Hays, Kansas

STATE OF COLORADO, COUNTY OF DENVER, ss.  
D. A. Coppedge

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *D. A. Coppedge*  
800 Security Life Bldg., Denver, Co. 80202

(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of September, 1974

*Mary Marston*

Notary Public.

My commission expires Nov. 22, 1975

# WELL LOG

15-083-10300-0000

COMPANY Sunray D-X

SEC. 20 T. 22S R. 22W

FARM Bamberger

NO. 7

LOC. SW NE


TOTAL DEPTH 4491'

COUNTY Hodgeman

COMM. 2-5-63

COMP. 2-16-63

CONTRACTOR Garvey Drilling Company



CASING 9 5/8" @ 251' w/225 SX

5 1/2" @ 4484' w/100 SX

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

115' Surface Clay, Sand and Shale  
 500' Shale  
 779' Shale and Red Bed  
 794' Blaine Anhydrite  
 856' Red Bed  
 1045' Sand  
 1395' Shale and Red Bed  
 1430' Anhydrite  
 1660' Shale  
 2015' Shale and Shells  
 2325' Shale w/Lime Stks  
 2800' Lime  
 2915' Shale and Lime  
 3065' Shale and Lime Stks  
 3190' Shale  
 3390' Shale and Shells  
 3472' Shale and Lime  
 3670' Shale and Shells  
 3750' Shale  
 3805' Shale and Lime  
 4195' Lime  
 4280' Lime and Shale  
 4491' Lime  
 4491' RTD

RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC 14 1973  
 CONSERVATION DIVISION  
 Wichita, Kansas

State of Kansas

County of Barton

ss

I, Verne A. Morris of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Bamberger #7 well.

*Verne A. Morris*

Subscribed and sworn to before me this 20th day of February 1963

My Commission Expires: October 24th, 1966

*Brantburg*  
NOTARY PUBLIC