

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-083-10304-0001

API NUMBER 6-29-63

LEASE NAME Bamberger

WELL NUMBER 11

 Ft. from S Section Line

C. SE NW Ft. from E Section Line

SEC. 11 TWP. 20 RGE. 22 (E) or (W)

COUNTY Hodgeman

Date Well Completed 6-29-63

Plugging Commenced 1-21-94

Plugging Completed 1-21-94

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Berexco, Inc.

ADDRESS Box 723 Hays, Kansas 67601

PHONE#(913 628 6101 OPERATORS LICENSE NO. 5363

Character of Well Inj.

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-21-94 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4550

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	.0	258	8 5/8		None
	Casing	0	4528	5 1/2		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Set packer at 775.70'. Rig up Mercury Wireline perf 4 holes at 750'. Run 141 jts. open ended 4424.36'. Spot 100 sk. 65/35 pos, 8% gel. Pull 46 jts. to 2967.95'. Spot 100 sk. 65/35 posmix, 8% gel. Pull 46 jts. to 1525.75'. Mix 115 sk. 65/35 pos, 8% gel. Circulate to surface Hook to 5 1/2. Mix 80 sk. 65/35 pos, 8% gel. Max. pressure 150# Shut in 100#. Hook to 8 5/8. Mix 150 sk. 65/35 pos, 8% gel. Max. pressure 500#. Shut in 200#.

Name of Plugging Contractor Berexco, Inc. License No. 5363

Address Box 723 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

STATE OF Kansas COUNTY OF Ellis

Mr. Ted Crawford (Employee of Operator) (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Ted Crawford

(Address) Box 723 Hays, Ks 67601

NOTARY PUBLIC - State of Kansas
ROSEMARY SMITH
My Appt. Exp. 5-1-1995

SUBSCRIBED AND SWORN TO before me this 26 day of January, 19 94

Rosemary Smith
Notary Public

My Commission Expires: 5-1-1995

USE ONLY ONE SIDE OF EACH FORM

RECEIVED
STATE CORPORATION COMMISSION
JAN 27 1994
1-27-94
CONSERVATION DIVISION
Wichita, Kansas