


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Hodgman County. Sec. 19 Twp. 22 Rgs. 22 (E) (W)
SE NE
Location as "NE/CNWSW" or footage from lines
Lease Owner Braden Deem, Inc.
Lease Name Oppy #2 Well No.
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 10/13/72 19
Plugging completed 2/21/73 19
Reason for abandonment of well or producing formation depleted.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eves
Producing formation Depth to top Bottom Total Depth of Well 4595 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	273	none
				5 1/2"	4590	2231'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, sanded hole to 4190' and set 5 sacks cement.
Shot pipe at 3511', 3384', 3259', 3132', 2998', 2812', 2627',
2446', pulled 70 joints. Allied pumped 8 sacks gel, 70 sacks
cement, 7 sacks gel and 50 sacks cement to plug well.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
MAR 12 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor VOTH CASING PULLING
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, SS.
WALTER VOTH (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) X Walter Voth

CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 1st day of March, 1973

My commission expires



MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Margaret Melcher
Notary Public.

023-01 PR-1

Sunray DX Oil Company
Tulsa, Oklahoma

Tulsa, Oklahoma
May 10, 1962

Contractor: Stickle Drilling Company
Date Commenced: April 27, 1962
Date Completed: May 8, 1962

Ethel Oppy No. 2
Ctr. SE NE Sec. 19-22S-22W
Hodgeman County, Kansas

DRILLER'S LOG

Depth Figures Indicate Base of Formation:

Shale	274
Shale and red bed	1310
Shale and shells	2400
Lime and shale	2545
Lime	2658
Lime and shale	2752
Lime	2895
Shale w/lime streaks	3025
Shale and lime	3868
Lime	3965
Shale and chalk	4037
Lime	4408
Lime and shale	4486
Lime and chert	4593 TD

RECEIVED
STATE CORPORATION COMMISSION

AUG 29 1972

CONSERVATION DIVISION
Wichita, Kansas

I, Fred E. Stickle, hereby certify the above to be a true and complete Driller's Log of Sunray DX Oil Company's Ethel Oppy, Well No. 2, Center of SE/4 of NE/4 of Section 19-22S-22W., Hodgeman County, Kansas.

Edith A. Lawver
Notary Public

Fred E. Stickle
FRED E. STICKLE

My Commission expires March 24, 1964.