


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission

P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Hodgman County, Sec. 19 Twp. 22 Rge. 22 (E) (W)  
Location as "NE/CNWSW" or footage from lines NE NE  
Lease Owner Braden Deem, Inc.  
Lease Name Oppy #3 Well No.  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 8/13/72 19  
Plugging completed 2/21/73 19  
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eves  
Producing formation Depth to top Bottom Total Depth of Well 4567 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	224	none
				5 1/2"	4548	3347

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded hole and set 5 sacks cement. Shot pipe at 3446', 3350', pulled 105 joints. Allied pumped 8 sacks gel, 70 sacks cement, 7 sacks gel and 50 sacks cement to plug well.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 6 1973  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
CHASE, KANSAS (Address) 73

SUBSCRIBED AND SWORN TO before me this 1st day of March, 1973

My commission expires  
MARGARET MELCHER  
NOTARY PUBLIC  
Rice County, Kansas  
My Commission Expires  
Feb. 15, 1975

Margaret Melcher  
Notary Public.

Sunray DX Oil Company  
Tulsa, Oklahoma

Tulsa, Oklahoma  
June 20, 1963

Contractor: Stickle Drilling Company

Oppy No. 3

Date Commenced: June 6, 1963

NE NW NE Sec. 19-22S-22W

Date Completed: June 15, 1963

Hodgeman County, Kansas

DRILLER'S LOG

Depth Figures Indicate Base of Formation:

Shale and shells	255
Clay and shale	460
Red bed, shale and sand	1469
Anhydrite	1507
Shale	1550
Shale and shells	2067
Shale	2404
Shale with lime	2565
Shale and lime	2650
Lime	2768
Lime and shale	3070
Shale and lime	3560
Shale	3730
Lime and shale	4050
Lime	4562 TD
TD corrected by electric log	4561

RECEIVED  
STATE CORPORATION COMMISSION

AUG 29 1972

CONSERVATION DIVISION  
Wichita, Kansas

I, Fred E. Stickle, hereby certify the above to be a true and complete Driller's Log of Sunray DX Oil Company's Oppy No. 3 Well, NW NE, Section 19-22S-22W, Hodgeman County, Kansas.

  
FRED E. STICKLE

  
Notary Public

My Commission Expires January 11, 1967