


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market
Wichita, Kansas

Hodgman County, Sec. 19 Twp. 22 Rge. 22 (E) W (W)

Location as "NE/CNW/SW" or footage from lines G NW NW
Lease Owner Quality Oil Company
Lease Name Miller Well No. 3
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 11/22/67 _____ 19____
Plugging completed 11/28/67 _____ 19____
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eves
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4585 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	278'	none
				4-1/2"	4585'	2487'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pulled tubing and rods. Checked hole to 4544', ran sand to 4300' and mixed and dumped 4 sacks of cement. Had hole loaded, shot pipe at 2500', pulled 46 joints. Pumped 10 sacks of mud at 1000', pulled to 900' and pumped in 100 sacks of cement. Pulled to 400' and pumped 5 sacks mud, pulled to 275' and pumped in 25 sacks of cement. Pulled rest of pipe, set 10' rock bridge at 55' to 45' and dumped 15 sacks of cement. Talled pipe and moved off location.

Plugging Complete.

RECEIVED
STATE CORPORATION COMMISSION
DEC 20 1967
12-20-67
CONSERVATION DIVISION
WICHITA, KANSAS

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of December, 19 67

My commission expires February 15, 1971
Margaret Melcher Notary Public.

ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY
 705 4th Natl Bank Bldg
 Wichita 2, Kansas
 LOCATION: C NW NW 19-22-22, Hodgeman County, Kansas
 Miller No. 3

Rotary Drilling Commenced 7-2-63

Rotary Drilling Completed 7-16-63

CONTRACTOR: PICKRELL DRILLING COMPANY
 Wichita, Kansas

CASING RECORD: 278' (10 jts.) 8 5/8" Surface Casing set with 175 sacks cement.
 Circulated. (140 jts) 4 1/2" casing set at 4585 with 165 sacks
 cement. Completed at 8:50 A.M. July 16, 1963.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

70	Clay & Post Rock	<u>C. F. S.</u>
150	Shale & Shells	4462
260	Shale & Shells, Sandy	4473
278	Sand Rock	4540
649	Shale	4545
950	Red Bed	4548
1220	Sand	4553
1430	Shale & Sand	4558
1475	Shells & Shale	4562
1515	Anhydrite	4566
1950	Shale & Shells	4571
2330	Lime & Shale	4576
2895	Lime	4600
3915	Shale & Lime	
4430	Lime	<u>Slope Test</u>
4473	Lime & Shale	1500
4535	Lime	2500
4548	Mississippian	3500
4555	Mississippian Chert	4000
4558	Lime & Chert	
4562	Chert	
4600	Mississippian Chert - RTD	<u>S. L. M.</u>
		2453
		3386
		4241

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 22 1967
 CONSERVATION DIVISION
 WICHITA, KANSAS

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. SEBITS Attorney-in-Fact

STATE OF KANSAS }
 COUNTY OF SEDGWICK } ss.:

On this 19th day of July, 19 63, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966

Maxine Blackman
 Maxine Blackman Notary Public