


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
213 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Hodgeman County. Sec. 7 Twp. 22S Rge. 22W (E) (W)  
Location as "NE/CNWxSWx" or footage from lines. C SW NW  
Lease Owner Sun Oil Company  
Lease Name Gus Miller "A" Well No. 3  
Office Address 1720 S. Bellaire, Suite 300, Denver, CO 80222  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 5-28 19 62  
Application for plugging filed 1-15 19 75  
Application for plugging approved 1-17 19 75  
Plugging commenced 1-24 19 75  
Plugging completed 1-28 19 75  
Reason for abandonment of well or producing formation State Regulations  
Require Plugging  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence F. Thomas  
Producing formation Mississippi Depth to top 4604 Bottom 4621 Total Depth of Well 4621 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	265	8 5/8	265	0
		0	4620	5 1/2	4620	2509

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Dumped 4 sacks of sand on plug. Shot off 5 1/2" casing. Pulled 2509' of 5 1/2" casing. Displace hole with 2 sacks of hulls, 50 sacks of cement, 10 sacks of gel, 35 sacks of cement and 10 sacks of gel. Released plug and displace hole with 10 sacks of cement to the surface.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 31 1975  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor \_\_\_\_\_  
Address \_\_\_\_\_

STATE OF Colorado, COUNTY OF Denver, ss.  
D. A. Coppedge (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. A. Coppedge

(Address)

SUBSCRIBED AND SWORN TO before me this 29<sup>th</sup> day of January, 19 75

Mary Marson

Notary Public.

My commission expires Nov. 22, 1975

WELL LOG

15-083-10241-0000

PR-4

COMPANY SUNRAY D-X OIL COMPANY

SEC. 7 T.22S R. 22W

FARM GUS MILLER "A" NO. 3


LOC. C-SW, NW

TOTAL DEPTH 4621'

COUNTY HODGEMAN CO., KANSAS

COMM. May 14, 1962 COMP. May 28, 1962

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8-5/8" @ 265' w/200 sax.  
5 1/2" @ 4620' w/125 sax.

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 17 1962  
CONSERVATION DIVISION  
Wichita, Kansas

40	Surface soil & post rock
935	Shale
1135	Sand
1470	Shale
1515	Anhydrite
1844	Shale
2407	Shale & lime
2482	Lime
2590	Lime & shale
2660	Lime
2742	Shale
3203	Shale & lime
3370	Shale & lime w/chalk streaks
3895	Shale & lime
4258	Lime
4411	Lime & shale
4428	Lime
4523	Shale & lime
4604	Mississippi lime
4621	Lime & shale
4621	T. D.

State of KANSAS }  
County of BARTON } ss

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state the above and foregoing is a true and correct copy of the log of the #3 G. MILLER "A" well.

*Verne A. Morris*

Subscribed and sworn to before me this 19th day of June 19 62

My Commission Expires: November 12, 1962

*Garvey*  
NOTARY PUBLIC