


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Hodgeman County. Sec. 7 Twp. 22S Rge. (E) 22 (W)
Location as "NE/CNW&SW4" or footage from lines C NE SE
Lease Owner Sunray DX Oil Company
Lease Name Gustav Miller Well No. 7
Office Address 321 West Douglas, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed _____ 19____
Application for plugging filed 5-27 1963
Application for plugging approved 5-28 1963
Plugging commenced 5-26 1963
Plugging completed 5-26 1963
Reason for abandonment of well or producing formation Non Commercial

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Hugh Scott, Sublette, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4604 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TD	SIZE	PUT IN	PULLED OUT
<u>Lsg. Kansas City</u>	<u>Water</u>	<u>3956</u>	<u>4254</u>	<u>8-5/8"</u>	<u>247'</u>	<u>0'</u>
<u>Marmaton</u>	<u>Water</u>	<u>4328</u>	<u>4358</u>			
<u>Mississippi</u>	<u>Water</u>	<u>4565</u>	<u>T.D.</u>			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud from total depth to 225' and set wood plug with 1/4 sack of hulls and 30 sacks of cement. Filled with heavy mud to 40' and set wood plug with 1/4 sack of hulls and 15 sacks cement to surface. Dumped 5 sacks of cement in rat hole and mouse hole. Well plugged and abandoned.

RECEIVED
STATE CORPORATION COMMISSION

JUN 3 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Stickle Drilling Company
Address 1100 Bitting Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
GARY W. PIERCE (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gary W. Pierce

321 West Douglas, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of May, 1963

My commission expires July 13, 1963
W. Montgomery Notary Public.

Sunray DX Oil Company
Tulsa, Oklahoma

Tulsa, Oklahoma
May 28, 1963

Contractor: Stickle Drilling Company
Date Commenced: May 15, 1963
Date Completed: May 25, 1963

Gus Miller No. 7
NE SE Sec. 7-22S-22W
Hodgeman County, Kansas

DRILLER'S LOG

Depth Figures Indicate Base of Formation:

Sand and shale	248
Shale	305
Red bed and shale	950
Sand and shale	1120
Red bed and shale	1425
Shale	2064
Shale and lime	2599
Lime	2863
Lime and shale	2962
Shale	3539
Shale and chalk	3750
Shale and lime	4010
Lime and shale	4117
Lime	4576
Chert	4606 TD
TD corrected by electric log	4604

I, Fred E. Stickle, hereby certify the above to be a true and complete Driller's Log of Sunray DX Oil Company's Gus Miller No. 7 Well, NE SE Section 7-22S-22W, Hodgeman County, Kansas.

Fred E. Stickle
FRED E. STICKLE

M. M. Mearns
Notary Public

My Commission Expires January 11, 1967

RECEIVED
STATE CORPORATION COMMISSION

JUN 3 1963

CONSERVATION DIVISION
Wichita, Kansas