


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Hodgeman County, Sec. 7 Twp. 22 Rge. 22 (E) W(W)
Location as "NE/CNW/SW" or footage from lines C SW NE
Lease Owner Sun Oil Company
Lease Name Gustav Miller "A" Well No. 4
Office Address 1720 S. Bellaire, Suite 300, Denver, CO 80222
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 9-10 19 62
Application for plugging filed 1-17 19 75
Application for plugging approved 1-17 19 75
Plugging commenced 1-20 19 75
Plugging completed 1-28 19 75
Reason for abandonment of well or producing formation State regulations require plugging
If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence F. Thomas
Producing formation Mississippi Depth to top 4563 Bottom 4568 Total Depth of Well 4655 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	264	8 5/8	264	0
		0	4652	5 1/2	4652	2761

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped 40 feet of sand to plug back total depth of 4543'.
Pulled 86 joints of 5 1/2" casing. Displaced hole with 2 sacks of hulls, 50 sacks of cement, 10 sacks of gel, 35 sacks of cement and 10 sacks of gel. Released plug and displaced hole with 10 sacks of cement. Capped to surface.

RECEIVED
STATE CORPORATION COMMISSION

JAN 31 1975

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Charlie Crowe Drilling Company
Address P. O. Box 706, Hays, KS

STATE OF Colorado, COUNTY OF Denver, ss.

D. A. Coppedge (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. A. Coppedge

SUBSCRIBED AND SWORN before me this 29th day of January, 19 75

(Address)

Mary Marson

Notary Public.

commission expires My Commission expires 12/22, 1975

WELL LOG

15-083-10242-0000

COMPANY **SUNRAY D-X OIL COMPANY**

SEC. 7 T-22S R. 22W

FARM **G. MILLER "A" NO. 4**

LOC. **C-MSW, NE**


TOTAL DEPTH **4655'**

COUNTY **HODGEMAN CO., KANSAS**

COMM. **June 7, 1962**

COMP. **June 21, 1962**

CONTRACTOR **GARVEY DRILLING COMPANY**



CASING **8-5/8" @ 264' w/200 sax.
5 1/2" @ 4652' w/100 sax.**

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

RECEIVED
STATE CORPORATION COMMISSION
JAN 17 1975
CONSERVATION DIVISION
Wichita, Kansas

264	Post rock, clay, sand & shale
345	Shale
834	Shale & shells
845	Blaine anhydrite
1190	Shale, shells & sand
1493	Shale & shells
1532	Anhydrite
1700	Shale
2280	Shale & shells
2422	Shale & lime
2901	Lime
2999	Lime & shale
3425	Shale & lime
3756	Lime & shale
4247	Lime
4272	Lime & chert
4411	Lime
4570	Lime & shale
4642	Cherty lime
4655	Shale
4655	T. D.

State of KANSAS }
County of BARTON } ss

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state the above and foregoing is a true and correct copy of the log of the #4 G. MILLER "A" well.

Subscribed and sworn to before me this 12th day of July 1962

My Commission Expires: November 12, 1962

Verne A. Morris
[Signature]
NOTARY PUBLIC