


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Hodgeman County, Sec. 27 Twp. 22 Rge. 22 (X) W (W)  
Location as "NE/CNW&SWK" or footage from lines C SE NW  
Lease Owner Cities Service Oil Company  
Lease Name Hamm "C" Well No. 3  
Office Address Box 308, Great Bend, Kansas 67530  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed May 5 19 63  
Application for plugging filed November 25 19 70  
Application for plugging approved November 30 19 70  
Plugging commenced January 7 19 71  
Plugging completed January 15 19 71  
Reason for abandonment of well or producing formation Uneconomical

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar Eves  
Producing formation Mississippi Depth to top 4429' Bottom 4431' Total Depth of Well 4431 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	286'	None
				5-1/2"	4429'	2825.38'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sand	- 4431-4400'
5 Sacks Cement	- 4400-4360'
Mud	- 4360- 510'
25 Sacks Gel & 3 Sacks Hulls	- 510- 500'
150 Sacks Cement	- 500- 0'

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 21 1971  
CONSERVATION DIVISION  
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Company  
Address Box 364, Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.  
W. J. Devaney (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed, and that the same are true and correct. So help me, God.

(Signature) [Signature]  
Box 308, Great Bend, Kansas 67530 (Address)

Subscribed and sworn to before me this 20th day of January 19 71



[Signature] Notary Public.

My commission expires June 3, 1973

15-083-10100-0000

DRILLER'S LOG

Imperial Oil Company  
780 Fourth National Building  
Wichita, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 30 1970  
CONSERVATION DIVISION  
Wichita, Kansas

HANN "C" NO. 3  
C SE NW Sec. 27-22S-22W  
Hodgeman County, Kansas

Total Depth: 4431'

Elevation: 2173 K.B.

Commenced: 4/26/ 63 Completed: 5/5/63

Contractor: Imperial Oil of Kansas, Inc.

Wichita 2, Kansas

Casing Record: Set 8-5/8" surface pipe at 286' with 200 sacks cement  
Set 5-1/2" production pipe at 4429' with 150 sacks Posmix

Figures indicate bottom of formations:

Tops

Shale & Sand	288'	Heebner	3746 (-1575)
Shale & Shells	648'	Toronto	3763 (-1590)
Anhydrite	656'	Lansing	3830 (-1657)
Shale & Shells	785'	Marmaton	4186 (- 2013)
Sand	995'	Cherokee Shale	4330 (-2157)
Shale & Shells	1333'	Mississippi (Osage)	4428 (-2255)
Anhydrite	1355'	RTD	4431 (-2258)
Shale & Shells	2360'		
Shale & Lime	3895'		
Lime	4419'		
Lime & Chert	4431'		

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL COMPANY

By Raymond R. Dombaugh  
Raymond R. Dombaugh

Subscribed and sworn to before me this 15th day of May, 1963.

My Commission Expires:

July 5, 1966

Bette J. Sycott  
Bette J. Sycott, Notary Public