

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Hodgeman County, Sec. 25 Twp 22S Rge. XE 22 (W)

Location as "NE/CNW/SW" or footage from lines C SE NE
Lease Owner Pickrell Drilling Company
Lease Name Ruff "B" Well No. 2
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 1 1971
Application for plugging filed February 1 1971
Application for plugging approved February 1 1971
Plugging commenced February 1 1971
Plugging completed February 1 1971
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves
Producing formation Depth to top Bottom Total Depth of Well 4537 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	276'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom Plug @ 800' w/80 sacks, Plug @ 270' w/25 sacks,
Top Plug @ 45' w/15 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
FEB 8 1971
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Building, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts
705 Fourth National Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 4th day of February, 1971



January 19, 1973

Esther Lamore
Notary Public.

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Building
Wichita, Kansas 67202

Rotary Drilling Commenced 1/21/71

Rotary Drilling Completed 2/1/71

LOCATION: Ruff "B" No. 2, C SE NE Section 25-22S-22W
Hodgeman County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: Run 13 Jts. 8-5/8" surface casing set @ 276' KB. Cemented with
150 sacks cement. Completed 6:45 P.M. Circulated.

No oil string run. D & A, Plugged 1:00 P.M. February 1, 1971.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

130	Post Rock - Shale		<u>C.F.S.</u>
277	Shale & Shells		4310
540	Shale		4330
755	Red Beds		4460
770	Blaine		4476
860	Red Beds - Shale		4520
1065	Sand		4527
1410	Shale - Shells		4532
1416	Shale		4537
1445	Anhydrite		
1735	Shale & Shells		
2210	Shale		<u>S.L.M.</u>
2772	Lime		
3105	Lime & Shale	Board	3889.37
3645	Shale & Lime	Strap	3887.09
3890	Lime & Shale		2.28 Difference
4532	Lime		
4537	Cherty Lime, RTD		
			<u>Slope Tests</u>
			2000
			2500
			3000
			3500
			4000
			4500

RECEIVED
STATE CORPORATION COMMISSION
FEB 9 1971
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 4th day of February, 19 71, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: January 19, 1973

Esther Lamone
Esther Lamone Notary Public