


STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Hodgman County. Sec. 25 Twp. 22 Rge. 22 (E) (W)
Location as "NE/CNW&SW" or footage from lines. 150 N of C NW SE
Lease Owner. Pickerell Drilling Company
Lease Name. Mooney F#1 Well No.
Office Address. Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed. 19
Application for plugging filed. 19
Application for plugging approved. 19
Plugging commenced. 5/24/75 19
Plugging completed. 5/31/75 19
Reason for abandonment of well or producing formation. depleted.

If a producing well is abandoned, date of last production. 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well. Thomas
Producing formation. Depth to top. Bottom. Total Depth of Well. 4549 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUL IN	PULLED OUT
				8-5/8	253	none
				5 1/2"	4547	2491

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole and ran sand to 4500', ran 5 sacks cement. Shot pipe at 2803', 2511', pulled 76 joints. Mixed 50 sacks cement, displaced 23.46 barrels water to 900', mixed 35 sacks cement, displaced with 12 barrels water to 500', mixed 10 sacks cement to bottom of cellar, 40'.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor. KELSO CASING PULLING
Address. CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE ss.
R. DARREL KELSO (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) R. Darrel Kelso
CHASE, KANSAS (Address)

Subscribed and sworn to before me this 5th day of June, 1975

Margaret Melcher
Notary Public.

My commission expires
MARGARET MELCHER
Rice County, Ks.
My Comm. Exp. Feb. 15, 1979

RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1975
CONSERVATION DIVISION
Wichita, KS 67203

6-9-75

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Building
Wichita, Kansas 67202

Rotary Drilling Commenced 2/9/70

Rotary Drilling Completed 2/19/70

LOCATION: Mooney "F" No. 1, C NW SE Section 25-22S-22W
Hodgeman County, Kansas

CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

CASING RECORD: Run 12 Jts. 28# 8-5/8" surface casing set @ 253' KB. Cemented with 165 sacks. Completed 2:30 PM. Circulated.

Run 141 Jts. 5-1/2" OD 14# Casing set @ 4547'. Cemented w/125 sacks 50-50 Pozmix 4% gel followed by 35 sacks common. Plug down at 3:30 PM February 19, 1970.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

65	Post Rock	<u>C.F.S.</u>	
253	Shale & Shell		4530
400	Shale, etc.		4535
795	Shale & Red Bed		4540
805	Blaine		4545
1060	Sand		
1439	Shale		
1472	Anhydrite	<u>S.L.M.</u>	
2100	Shale	Board	4111.27
2460	Shale & Lime	Strap	4110.96
2860	Lime & Shale		.31 Difference
3125	Shale & Lime		
3320	Lime & Shale		
3465	Shale & Lime	<u>Slope Tests</u>	
3575	Lime & Shale		2000
4055	Shale & Lime		2500
4125	Lime & Shale		3000
4220	Shale & Lime		3500
4298	Lime		4000
4483	Lime & Shale		4500
4548	Lime, RTD		

RECEIVED
STATE CORPORATION COMMISSION
MAY 9 1970
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 25th day of February, 19 70, before me the undersigned, a Notary Public, in and for

the County of Sedgwick, State of Kansas, personally appeared C. W. Sebitts, to me known to be the person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument, and acknowledged to me that he executed the same as his free and voluntary act and deed, and as its true and legal act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.



January 19, 1973

Esther Lamone
Esther Lamone Notary Public