

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-083-21,131-0000

LEASE NAME Ruff

WELL NUMBER 1

SPOT LOCATION C W/2 NE/4

SEC. 25 TWP. 22S RGE. 22 (~~XXXX~~W)

COUNTY Hodgeman

Date Well Completed 3/16/84

Plugging Commenced 3/16/84

Plugging Completed 3/16/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR DaMar Resources, Inc.
ADDRESS P. O. Box 70
Hays, KS 67601

PHONE (913) 625-0020 OPERATORS LICENSE NO. 9067

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes.

Which KCC/KDHE Joint Office did you notify? District #1.

Is ACO-1 filed? No. If not, is well log attached? Yes.

Producing formation _____ Depth to top _____ bottom _____ T.D. 4546'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From -0-	To 1417'	Size 8 5/8"	Put in 1417'	Pulled out -0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Mud laden fluid 4546'-1460'

50 sks cement @ 1460'

40 sks cement @ 720'

10 sks cement @ 40'

15 sks cement @ Rat Hole

10 sks cement @ Mouse Hole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750
Address P. O. Box 506
Russell, KS 67665

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Joe K. Branum, (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well **RECEIVED** that the same are true and correct, so help me God.

STATE CORPORATION COMMISSION

(Signature) Joe K. Branum

(Address) P. O. Box 506

Russell, KS 67665

MAR 27 1984

SUBSCRIBED AND SWORN TO before me this 26th day of March, 1984
Wichita, Kansas

DENISE S. REYNOLDS
Notary Public
STATE OF KANSAS
My Appointment Expires:
2-13-85

Denise S. Reynolds, Notary Public

My Commission expires: February 13th, 1985.

EMPHASIS OIL OPERATIONS

P. O. BOX 506

RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: DaMar Resources, Inc.
P. O. Box 70
Hays, KS 67601

CONTRACTOR: Emphasis Oil Operations
P. O. Box 506
Russell, KS 67665

LEASE: Ruff WELL: #1

LOCATION: C W/2 NE/4
Section 25-22S-22W
Hodgeman County, KS

ROTARY TOTAL DEPTH: 4546'

ELEVATION:

COMMENCED: 3/5/84

DATE COMPLETED: 3/16/84

CASING: 8 5/8" @ 1417' with 500 sks cement

STATUS: Dry Hole


DEPTHS & FORMATIONS

(All measurements from K.B.)

Top Soil & Sand	30'	Shale	3573'
Shale	1414'	Shale & Lime	3705'
Anhydrite	1447'	Shale	3915'
Shale	2181'	Lime & Shale	4527'
Quartz & Shale	2206'	Lime (R.T.D.)	4546'

STATE OF KANSAS)
) ss:
COUNTY OR RUSSELL)


Joe K. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.



Joe K. Branum

Subscribed and sworn to before me this 26th day of March, 1984.

My Commission Expires: February 13th, 1985.





Denise S. Reynolds, Notary Public

RECEIVED
STATE CORPORATION COMMISSION
MAR 27 1984
CONSERVATION DIVISION
Wichita, Kansas