

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION

JUL 2 1974

CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Adams of Sun has this

date requested permission to plug the following described well:

Mr. Adams guarantees payment of the plugging fee.Operator's full Name: Sun Oil CompanyComplete Address: 800 Security Life Bldg., Denver, ColoradoLease Name: Bamberger Well No. 12Location: NE SW Sec. 20 Twp. 22 Rge. 22 (E) (W)County: Hodgeman Total Depth 4535' Oil Well XGas Well Input Well SWD Well D & A Lost Hole Mr. Adams was instructed to plug the well as follows:8 5/8" to 260' circulated w/ cement. 5 1/2" to 4520' cemented.Open hole 4535' to 4520' Plug bottom w/ sand & 5 sacks cement.Top of cement 4480' Mud 4480' to 850'Spot 80 sacks cement 850' to 550' Mud 550' to 260'Spot 30 sacks cement 260' to 160' Mud 160' to 45'Plug, H_ulls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent