



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

FEB 27 1973

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Powell of Braden-Deem has this

date requested permission to plug the following described well:

Mr. Powell guarantees payment of the plugging fee.

Operator's full Name: Braden-Deem Inc.

Complete Address: 200 E 1st, Wichita, Kansas

Lease Name: E. Oppy Well No. 1

Location: SW NE Sec. 19 Twp. 22 Rge. 22 <sup>XX</sup>(E)(W)

County: Hodgeman Total Depth 4631' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Powell was instructed to plug the well as follows:

8 5/8" to 257' circulated w/ cement. 5 1/2" to 4630' cemented.

Top perforations 4282' Plug bottom w/ sand & 5 sacks cement.

Top of cement 4200' Mud 4200' to 700'

Spot 70 sacks cement 700' to 400' Mud 400' to 200'

Plug & 50 sacks cement 200' to 0'.

Very truly yours,

Conservation Division Agent