



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 27 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Powell of Braden-Deem has this
date requested permission to plug the following described well:

Mr. Powell guarantees payment of the plugging fee.

Operator's full Name: Braden-Deem Inc.

Complete Address: 200 E. 1st, Wichita, Kansas

Lease Name: E. Oppy Well No. 3

Location: NE NE Sec. 19 Twp. 22 Rge. 22 (E)(W)

County: Hodgeman Total Depth 4567' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Powell was instructed to plug the well as follows:

8 5/8" to 224' circulated w/ cement. 5 1/2" to 4548' cemented.

Open hole 4548' to 4567' Plug bottom w/ sand & 5 sacks cement

Top of cement 4480' Mud 4480' to 700'

Spot 70 Sacks cement 700' to 400' Mud 400' to 200'

Plug & 50 sacks cement 200' to 0'.

Very truly yours,

Conservation Division Agent