



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 14 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Glenn of Specter has this

date requested permission to plug the following described well:

Mr. Glenn guarantees payment of the plugging fee.

Operator's full Name: Specter Pipe & Supply

Complete Address: Box 169, Russell, Kansas

Lease Name: Percoco Well No. 2

Location: C NE SE Sec. 19 Twp. 22 Rge. 22 XX (E) (W)

County: Hodgeman Total Depth 4646' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Glenn was instructed to plug the well as follows:


8 5/8" to 262' circulated w/ cement. 5 1/2" to 4645' cemented.

1' of open hole Plug bottom w/ sand & 5 sacks cement.

Top of cement 4610' Mud 4610' to 450'

Spot 120 sacks cement 450' to 0'.

Very truly yours,


Conservation Division Agent