



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian

WICHITA, KANSAS 67217

RECEIVED  
STATE CORPORATION COMMISSION

AUG 14 1973

CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Glenn of Specter Pipe has this  
date requested permission to plug the following described well:

Mr. Glenn guarantees payment of the plugging fee.

Operator's full Name: Specter Pipe & Supply

Complete Address: Box 169, Russell, Kansas

Lease Name: Percoco Well No. 1

Location: C NW SE Sec. 19 Twp. 22 Rge. 22 (E)(W)

County: Hodgeman Total Depth 4670' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Glenn was instructed to plug the well as follows:


8 5/8" to 240' circulated w/ cement. 5 1/2" to 4669' cemented.

1' of open hole 1 Plug bottom w/ sand & 5 sacks cement.

Top of cement 4570' Mud 4570' to 450'

Spot 120 sacks cement 450' to 0'.

Very truly yours,

  
Conservation Division Agent