



15-083-10198-0000

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

NOV 30 1967

CONSERVATION DIVISION  
WICHITA, KANSAS

11-30-67

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Kelso of Quality Oil Co. has this

date requested permission to plug the following described well:

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: Quality Oil Company

Complete Address: 6320 Jaqueline, Wichita, Kansas

Lease Name: Miller Well No. 3

Location: C NW NW Sec. 19 Twp. 22 Rge. 22 (E) (W)

County Hodgeman Total Depth 4600' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Kelso was instructed to plug the well as follows:

8 5/8" to 278' circulated w/ cement. 4 1/2" to 4585' cemented

Top perforations 4308' Plug bottom w/ Sand & 5 sacks cement

Top of cement 4220' Mud 4220' to 900'

Spotted 100 sacks cement 900' to 550' Mud 550' to 270'

Spotted 25 sacks cement 270' to 170' Mud 170' to 45'

Plug, Halls & 15 sacks cement 45' to 0'

Very truly yours,

Charles A. Eves  
Conservation Division Agent