



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 27 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Powell of Braden-Deem has this

date requested permission to plug the following described well:

Mr. Powell guarantees payment of the plugging fee.

Operator's full Name: Braden-Deem Inc.

Complete Address: 200 Elst, Wichita, Kansas

Lease Name: Jocelyn Ewy Well No. 1

Location: SW SW Sec. 15 Twp. 22 Rge. 22 (SW) (W)

County: Hodgeman Total Depth 4443' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Powell was instructed to plug the well as follows:

8 5/8" to 256' circulated w/ cement. 5 1/2" to 4423' cemented.


open hole 4423' to 4443' Plug botttom w/ sand & 5 sacks cement.

Top of cement 4360' Mud 4360' to 700'

Spot 70 sacks cement 700' to 400' Mud 400' to 200'

Plug, Hulls & 50 sacks cement 200' to 0'.

Very truly yours,


Conservation Division Agent