

State of Kansas



15-083-30092-0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 10 1966

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Miller of L.J. Dreiling & Sons has this

date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: L.J. Dreiling & Sons, Inc.

Complete Address: Victoria, Kansas

Lease Name: Heimer Well No. 1

Location: SW SW Sec. 11 Twp. 22 Rge. 22 (E) (W)

County Hodgeman Total Depth 4460' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Miller was instructed to plug the well as follows:

- 8 5/8" to 225' circulated w/cement, T.D. 4460'
- Mud 4460' to 700' Spotted 30 sacks cement 700' to 600'
- Mud 600' to 275' Spotted 30 sacks cement 275' to 175'
- Mud 175' to 40' Plug, Hulls & 10 sacks cement 40' to 0'.

Very truly yours,

Edgar J. Eves
Conservation Division Agent