



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 18 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Hallam of Cities Service has this
date requested permission to plug the following described well:

Mr. Hallam guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company

Complete Address: Box 308, Great Bend, Kansas

Lease Name: Hann "C" Well No. 3

Location: C SE NW Sec. 27 Twp. 22 Rge. 22 (E) (W)

County: Hodgeman Total Depth 4431' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hallam was instructed to plug the well as follows:

8 5/8" to 286' circulated w/ cement. 5 1/2" to 4429' cemented.

Open hole from 4429' to 4431' plug bottom w/ sand & 5 sacks cement.

Top of cement 4300' Mud 4300' to 500'

Spolt 150 sacks cement 500' to 0'

Very truly yours,

Conservation Division Agent