

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-083-21,151-0000

LEASE NAME Steinbring

WELL NUMBER 1-24

SPOT LOCATION 165' S of NE SE NW

SEC. 24 TWP. 22 RGE. 23 (E) or (W)

COUNTY Hodgeman

Date Well Completed 7-24-84

Plugging Commenced 7-24-84

Plugging Completed 7-24-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Landmark Oil Exploration

ADDRESS 105 S. Broadway, Suite 1040, Wichita, KS 67202

PHONE # (316) 265-8181 OPERATORS LICENSE NO. 6113

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #1

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation N/A Depth to top _____ bottom _____ T.D. 4643

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8 5/8 | 285' | None |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set. Fill hole with mud.

Spotted 50 sx cement @ 1560' thru drill pipe.

Spotted 50 sx cement @ 750' thru drill pipe.

Spotted 50 sx cement @ 330' thru drill pipe.

Spotted solid bridge plug, 1 sx hulls, and 10 sx cement @ 40' thru-
drill pipe.

Spotted 15 sx cement in rathole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc. License No. 5420

Address 401 East Douglas, Suite 500, Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Michael L. Considine (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) Michael L. Considine

(Address) 401 E. Douglas, Suite 500
Wichita, Ks. 67202

SUBSCRIBED AND SWORN TO before me this 9th day of August, 1984


Carolyn J. Tjaden
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

AUG 13 1984

CONSERVATION DIVISION
Wichita, Kansas
My Commission expires

CAROLYN J. TJADEN
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Expires Sept. 5, 1984



WHITE

AND ELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: Landmark Oil Exploration, Inc.
 105 S. Broadway, Suite 1040
 Wichita, KS 67202
 CONTRACTOR: White & Ellis Drilling, Inc., 401 E. Douglas, Suite 500,
 Wichita, Ks. 67202

Lease Name Steinbring Well No. #1-24
 Sec. 24 T. 22S R. 23W Spot 165' South of NE SE NW
 County Hodgeman State Kansas Elevation _____

Casing Record:

Surface: 8 5/8 @ 285' with 175 2% cc sx.

Production: _____ @ _____ with _____ sx.

Type Well: D & A Total Depth 4643'

Drilling Commenced 7-14-84 Drilling Completed 7-24-84

| Formation | From | To | Tops |
|-------------|------|------|----------------|
| Cellar | 0 | 7 | Anhydrite-1541 |
| Lime | 7 | 290 | |
| Sand, Shale | 290 | 2707 | |
| Shale, Lime | 2707 | 3103 | |
| Lime, Shale | 3103 | 4475 | |
| Shale, Lime | 4475 | 4643 | |

RECEIVED
 STATE CORPORATION COMMISSION

AUG 13 1984

CONSERVATION DIVISION
 Wichita, Kansas