


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Hodgeman County, Sec. 24 Twp. 22S Rge. 23 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SE/4 NE/4

Lease Owner Hoppe Oil & Gas Co., Inc.
Lease Name Mennonite Church Well No. 1
Office Address 2400 N. Woodlawn, Suite 211, Wichita, KS
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plot

dry hole
Date Well completed 12/29 1982
Application for plugging filed 12/29 1982
Application for plugging approved 12/29 1982
Plugging commenced 12/29 1982
Plugging completed 12/29 1982

Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered.
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi
Producing formation Depth to top Bottom Total Depth of Well
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Total depth 4665 feet. Set first plug at 870 feet with 70 sacks of 50/50 poz mix cement, 4% Gel and 3% Calcium Chloride; set second plug at 240 feet with 40 sacks; 10 sacks and a bridge at 40 feet and 10 sacks in the rathole. Job completed at 4:30 p.m. on December 29, 1982.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kaw Drilling Co., Inc.


STATE OF KANSAS COUNTY OF SEDGWICK, ss. contractor
K. S. Martin, President of Kaw Drilling Co., Inc. (employee of owner) or former operator
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) K. S. Martin
K. S. Martin, President 1010 Union Center
(Address) Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 3rd day of January, 1983.

My commission expires December 10, 1983

Mary Susan Whaley
Mary Susan Whaley, Notary Public



JAN 04 1983

CONSERVATION DIVISION
Wichita Kansas

OFFEROR:	Hoppe Oil & Gas Co., Inc.
CONTRACTOR:	Kaw Drilling Co., Inc.
WELL NAME:	#1 Mennonite Church
LOCATION:	SE/4 NE/4 Sec. 24-22S-23W Hodgeman County, Kansas
SPUD DATE:	December 17, 1982
COMPLETION DATE:	December 29, 1982

219	965	Shale
2420	3110	Shale and Shell
3110	3770	Shale and Lime
4275	4290	Lime
4290	4460	Lime and Shale
	4665	R.T.D.

Spud hole at 8:00 p.m. on December 17, 1982. Drilled 219 feet of 12 1/2 inch hole. Ran 5 joints of 8 5/8 inch casing. (Tallied at 204 feet.) Set at 216 feet with 175 sacks of common cement, 3% Gel and 2% Calcium Chloride. Plug down at 1:00 a.m. on December 18, 1982.

Total depth 4665 feet. Set first plug at 870 feet with 70 sacks of 50/50 poz mix cement, 4% Gel and 3% Calcium Chloride; set second plug at 240 feet with 40 sacks; 10 sacks and a bridge at 40 feet and 10 sacks in the rathole. Job completed at 4:30 p.m. on December 29, 1982.

RECEIVED
STATE CORPORATION COMMISSION

JAN 04 1983

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)

I, K. S. Martin, President of KAW DRILLING CO., INC., being first duly sworn and upon my oath, state that: I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

K. S. Martin
K. S. Martin, President

SUBSCRIBED AND SWORN to before me on this 3rd day of January, 1983.

Mary Susan Whaley
Mary Susan Whaley, Notary Public

My commission expires:
December 10, 1983

