

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-083-20668-0000

LEASE NAME Ruff

WELL NUMBER 1A

330' Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 23 TWP. 22s RGE. 22w or (W)

COUNTY Hodgeman

Date Well Completed 9-18-99

Plugging Commenced 9/28/98 11:30 AM

Plugging Completed 9/28/98 1:30 PM

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Buried Hills Production Co. Inc.

ADDRESS 1050 17th Street 1550 Denver, Colo. 80265

PHONE (303) 595-0125 OPERATORS LICENSE NO. 31961

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9/25/98 (date)

by Kevin Strube MIKE MAIER OW for (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? No

Producing Formation Mississippi Depth to Top 4382' Bottom 4411 T.D. 4411

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Casing	0	1326	8 5/8	1326'	None
	Casing	0	4382	4 1/2	4382'	2000'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Sand back to 4325' DUMP % SKS. of cement on top of sand.
Pull casing to 1400'. Mix 50 sks. of 60/40 posmix 6% gel. Displace with
5 sks. of gel. Pull pipe to 600'. Mix 50 sks. of cement. Pull pipe to 40'.
Mix 10 sks. of cement. Fill to top.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services Pratt, Ks. License No. 10-13-98

Address P.O. Box 963 Pratt, Ks. 67124


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Buried Hills Prod. Co., Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Dean Ives (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dean Ives

(Address) 1209 HANEY HAYS, KS



CHARLOTTE WEBER DESCRIBED AND SWORN TO before me this 8th day of Oct., 19 98

Charlotte Weber
Notary Public

My Commission Expires: 12-28-99