


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas



Hodgeman County, Sec. 19 Twp. 22 Rge. 23 ~~EX~~XXX (W)
Location as "NE/CNW%SW%" or footage from lines C NW/4 NE/4
Lease Owner Pickrell Drilling Company
Lease Name Craghead #1 Well No. #1
Office Address 705 Fourth National Bank Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4-10- 19 60
Application for plugging filed " 19 "
Application for plugging approved " 19 "
Plugging commenced " 19 "
Plugging completed " 19 "
Reason for abandonment of well or producing formation Dry and Abandoned

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merle A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4705 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	240'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with heavy mud to 238'.
Bridge hole and cemented with
20 sacks of cement. Then heavy
mud to 40'. Set plug and ce-
mented to the bottom of cellar
with 13 sacks of cement. Plugged
rat hole with 2 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
APR 14 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. W. Sebts (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *C. W. Sebts*
705 Fourth National Bank Building
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of April, 1960.

My commission expires August 13, 1961 *Ruth M. Sullivan* Notary Public.

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Building
Wichita 2, Kansas

Rotary Drilling Commenced 3-24-60

Rotary Drilling Completed 4-10-60

LOCATION: Craghead #1
C. NW/4 NE/4, Sec. 19-22S-23W
Hodgeman County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: 240' (6 jts.) Armco 8-5/8" spiral weld casing. Set at 240'.
Cemented with 175 sacks of cement. Cement circulated. Completed
8:30 P.M., 3-25-60.

Dry and abandoned.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

30	Clay	Circ. for Samples:	
85	Shale	4620'	
155	Sand	4625'	
240	Shale	4635'	
1005	Shale, Shells, Red Bed	4640'	
1025	Anhydrite	4645'	
1560	Shale, Shells	4655'	
2360	Lime, Shale	4666'	
2659	Lime	4670'	
2952	Lime, Shale, Chalk	4675'	
3070	Lime, Shale	4705'	
4070	Lime		
4635	Mississippi Dolomite	Slope Tests:	
4655	Mississippi	2000'	OO
4705	Rotary Total Depth	3000'	OO
		4000'	OO

S.L.M.

2000'	OK
3000'	OK
4000'	OK

RECEIVED
STATE CORPORATION COMMISSION
APR 14 1960
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By [Signature]
C. W. Sebitts, Partner

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 13th day of April, 1960, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: August 13, 1961

[Signature]
Notary Public

Ruth M. Sullivan