


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Hodgeman County. Sec. 19 Twp. 22S Rge. 23W E4  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines \_\_\_\_\_

C-SW SE NE  
Lease Owner Ram Petroleum Corporation  
Lease Name Craghead Well No. 2  
Office Address 800 Vickers KSB&T BLDG., Wichita, KS  
Character of Well (Completed as Oil, Gas or Dry Hole) 67202



Locate well correctly on above  
Section Plot

Dry Hole  
Date Well completed January 2, 1980  
Application for plugging filed Verbal Application 1980  
Application for plugging approved Verbal Approval 1980  
Plugging commenced January 2, 1980  
Plugging completed January 2, 1980  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production 1980

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4,642'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	532'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy rotary mud from 4,642 ft. (rotary total depth) to 900 ft. Set plug at 900 ft. and cemented with 50 sacks cement. Filled hole with heavy rotary mud from 900 ft. to 500 ft. Set plug at 500 ft. and cemented with 40 sacks cement. Filled hole with heavy rotary mud from 500 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 5 sacks cement in rat hole.

Plugging operations accomplished utilizing Sun Oil Well cementing pump truck through 4 1/2 inch drill pipe.

1-16-80

RECEIVED  
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oilwell Cementing, Inc.  
Box 169, Great Bend, Kansas 67530  
Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick  
Dean Britting, Agent (Employee of owner) or (owner or operator)


of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting  
200 N. Main, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of January, 1980

My commission expires July 25, 1982

Elsie Willison  
Elsie Willison - Notary Public.



KANSAS DRILLERS LOG

COMPANY Ram Petroleum Corporation

SEC. 19 T. 22S R. 23W

FARM Craghead NO. 2

LOC. C-SW SE NE

ROTARY TOTAL DEPTH 4,642'

COUNTY Hodgeman

COMM. December 20, 1979 COMP. January 2, 1980

CONTRACTOR H-30, INC. (Rig #2)

ISSUED January 14, 1980

CASING

10 3/4"

8 5/8" Set at 532' cemented w/285 sxs cement

ELEVATION 2,371' K.B.

5 1/2"

4 1/2"

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale and Sand	80'
Shale	600'
Shale and Sand	1,525'
Red Bed	1,624'
Anhydrite	1,666'
Shale	2,215'
Shale and Lime	2,490'
Lime and Shale	2,650'
Shale and Lime	2,755'
Lime and Shale	3,080'
Shale and Lime	3,170'
Lime and Shale	3,450'
Shale and Lime	3,605'
Lime and Shale	4,320'
Lime	4,642'
Rotary Total Depth	4,642'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

*Dean Britting*  
Dean Britting

State of Kansas }  
County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public  
in and for said county and state this 14th day of  
January, 1980.

RECEIVED  
NOTARY PUBLIC COMMISSION

JAN 16 1980

CONSERVATION DIVISION  
Wichita, Kansas



*Elsie Willison*  
Elsie Willison - Notary Public

My Commission Expires:

July 25, 1982