


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Pawnee County, Sec. 30 Twp. 22 Rge. (E) 17(W)
Location as "NE/CNW&SW&" or footage from lines C SE NE
Lease Owner Hudson Petroleum Co.
Lease Name Boyd Well No. 1
Office Address P. O. Box 333 Kansas City 3, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 7/31/64 1964
Application for plugging filed 7/31 1964
Application for plugging approved 7/31 1964
Plugging commenced 7/31/64 4 PM 1964
Plugging completed 7/31/64 5 PM 1964
Reason for abandonment of well or producing formation Dry
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Scott
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4250 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Viola</u>	<u>wtr</u>	<u>4240</u>	<u>4250</u>	<u>8 5/8</u>	<u>252</u>	<u>none</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug @ 700' W/25 sax cement
Plug @ 250' W/25 sax cement
Plug @ 45' W/15 sax cement & hulls to top of surface
2 sax cement in rat hole

RECEIVED
STATE CORPORATION COMMISSION

AUG 10 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF Florida COUNTY OF Dade ss.
Joseph Teichman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joseph Teichman
6045 Pine Tree Dr., Miami Beach, Fla.
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of August, 1964

Miriam Unge
Notary Public.

My commission expires _____

SHOLOM DRILLING COMPANY, INC.
6045 Pine Tree Drive
Miami Beach, Florida 33140

COMPANY: Hudson Petroleum Company.
FARM: Boyd
LOCATION: C SE NE Sec 30 T28S R17W, Pawnee County, Kansas
ROTARY DRILLING CONTRACTOR: Sholom Drilling Co., Inc.

COMMENCED: 7/20/64
COMPLETED: 7/31/64
I. P.: D & A

Rotary T. D.: 4250

Elevation:
Casing Record:
8 5/8" @ 252' W/175 sax

L O G

0	-	40	clay
40	-	390	shale
390	-	500	red bed and sand
500	-	585	red bed
585	-	655	sand
655	-	1137	red bed
1137	-	1160	Anhydrite
1160	-	1565	red bed and shale
1565	-	1735	shale
1735	-	3430	lime and shale
3430	-	3555	lime
3555	-	3735	lime and shale
3735	-	4153	lime
4153	-	4177	chert
4177	-	4203	chert, lime & shale
4203	-	4240	chert & shale
4240	-	4250	chert & lime
4250	-		Rotary T. D.

DST #1 4137-53 Rec 70' GCM
BHP 740-200#
FP 70-0#

#2 4148-77 Rec 180' mud
BHP 1400-1000#
FP 80-40 #

#3 4177-4200. Rec 25' GCM

RECEIVED
STATE CORPORATION COMMISSION

AUG 10 1964

CONSERVATION DIVISION
Wichita, Kansas

STATE OF FLORIDA)
COUNTY OF DADE) ss.

I, Joseph Telchman, President of Sholom Drilling Company, Inc., a corporation of the state of Oklahoma, domesticated in the State of Kansas, being first duly sworn under oath, says: That I have knowledge of the facts, statements, and matters herein contained of the above described well as filed and that the same are true and correct.

Joseph Telchman
Joseph Telchman

Subscribed and sworn to before me this 4th day of August, 1964

Miriam Inger
Notary Public