


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plat

Pawnee County, Sec. 3 Twp. 22S Rge. 17 ~~XX~~W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NW NW NW

Lease Owner Mtd-America Producers, Inc.
Lease Name Lewis Well No. 1
Office Address P.O. Box 18163, Oklahoma City, Okla. 73154
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole

Date Well completed Jan. 30 1981
Application for plugging filed Jan. 30 1981
Application for plugging approved Jan. 30 1981
Plugging commenced Jan. 31 1981
Plugging completed Jan. 31 1981
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3955'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1052'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug-set.

1st Plug 1000' w/65 Sks.
2nd Plug 240' w/30 Sks.
3rd Plug 40' w/10 Sks.
5 Sks. in rat hole

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor RoCo Drilling, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.
Richard L. Miller (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Richard L. Miller
1819 - 11th St., Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of February, 1981

Mary C. Cook
Notary Public.



February 28, 1983

CONFIDENTIAL

2-9-81

ROCO DRILLING, INC.

GREAT BEND, KANSAS 67530

P. O. BOX 11
 1819 ELEVENTH STREET
 TELEPHONE (316) 792-1383

DRILLERS WELL LOG

Lewis #1
 NW NW NW, Section 3-22S-17W
 Pawnee County, Kansas

Operator: Mid-America Producers, Inc.
 P.O. Box 18163
 Oklahoma City, Okla. 73154

Date Commenced: January 25, 1981
 Date Completed: January 30, 1981

Elevation: 2011' K.B.
 Total Depth: 3960'
 Loggers T.D. 3955'
 D & A

Casing: 8 5/8" @ 1052' w/450 Sks.

DEPTH		FORMATION	ELECTRIC LOG TOPS	
FROM	TO			
0	464	Surface Soil - Sand - Shells	Heebner	3449
464	579	Sand	Toronto	3469
579	1046	Shale - Sand	Brown Lime	3542
1046	1069	ANHYDRITE	Lansing	3552
1069	2000	Shale - Shells - Gyp	Arbuckle	3930
2000	3449	Lime - Shale	Electric Log T.D.	3955
3449	3455	HEEBNER SHALE		
3455	3542	Shale - Sand - Lime		
3542	3829	Lime - Shale		
3829	3930	Shale - Lime - Chert		
3930	3960	ARBUCKLE DOLOMITE		
	3960	Rotary Total Depth		

I, Richard L. Miller, certify this is a correct copy of the Driller's Log from the well drilled at the above location, to the best of my knowledge and belief.

Signed Richard L. Miller
 Richard L. Miller

REVISION
 FEB - 9 1981
 DIVISION
 Kansas