


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pawnee County. Sec. 1 Twp. 22 Rge. (E) 17 (W)
Location as "NE/CNW/SW" or footage from lines SE SE SW
Lease Owner Gulf Oil Corporation
Lease Name State Hospital Well No. 1
Office Address Box 661 Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4-8 19 54
Application for plugging filed 4-8 19 54
Application for plugging approved 4-8 19 54
Plugging commenced 4-9 19 54
Plugging completed 4-9 19 54
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - 1954
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Arbuckle Depth to top 3919 Bottom 3956 Total Depth of Well 3956 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1023'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole filled TD to 300' with heavy rotary mud. Set bridge at 300', consisting of HOWCO cementing plug and cotton seed hulls. Spotted 20 sx. cement thru DP on bridge. Filled hole with mud to 25' of surface set bridge and capped with 10 sx. cement. Well plugged and abandoned.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Musgrove Petroleum Corporation
Address 407 KFH Building, Wichita, Kansas.

STATE OF Kansas, COUNTY OF Rice, SS.
W. H. Duley (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. H. Duley
Box 544 Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of April, 1954

My commission expires April 14, 1956
STATE CORPORATION COMMISSION Notary Public.

24-7966-6 3-53-20M

APR 20 1954

CONSERVATION DIVISION
Wichita, Kansas

4-20-54

PLUGGING
SEE SEC 1 T 22 R 17 W
BOOK PAGE 25 LINE 43

CONTRACTOR'S WELL LOG

COMPANY:	Gulf Oil Corporation
CONTRACTOR:	Musgrove Petroleum Corporation
FARM:	STATE HOSPITAL #1
LOCATION:	SE SE SW, Section 1-22S-17W Pawnee County, Kansas
COMMENCED:	March 26, 1954
COMPLETED:	April 8, 1954

0	352	Sand, shale & shells
352	432	Shale & shells
432	536	Sand
536	659	Shale, shells, red bed.
659	882	Shale & red bed
882	1018	Shale
1018	1039	Anhydrite
1039	1610	Shale & shells
1610	1700	Shale & lime
1700	1887	Shale & shells
1887	2085	Lime & shale
2085	2240	Lime
2240	3424	Lime & shale
3424	3852	Lime
3852	3895	Lime & shale
3895	3930	Lime
3930	3956	Arbuckle
	3956'	Rotary Total Depth

Set 8-5/8" surface casing at 1022' with 460 sacks cement.

Dry and Abandoned.

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the STATE HOSPITAL #1, SE SE SW of Section 1-22S-17W, Pawnee County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

BY *Gordon L. Koelling*
Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 14th day of April, 1954.

William S. ...
Notary Public

My commission expires September 24, 1956.

PLUGGING
FARM SEC 1-22-17W
BOOK PAGE 25 LINE 43