


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plot

Harvey County. Sec. 25 Twp. 22S Rge. 3W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C. NE/4 NE/4
Lease Owner Vincent Oil Corp.
Lease Name Stucky #1 Well No.
Office Address 230 O. W. Garvey Bldg, Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole)

Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 1-15-81 19
Plugging completed 1-23-81 19
Reason for abandonment of well or producing formation

Depleted
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Thompson
Producing formation Depth to top Bottom Total Depth of Well 3215
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4	212	None
				4-1/2	3214	2582

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged off bottom. Pushed plug to 3150'. Sanded to 3100' and set 4 sacks cement. Made shot at 2600. Pulled total of 66 joints. Allied plugged the well with 4 sacks hulls, 13 sacks gel, 50 sacks cement, 2 sacks gel, 1 sack hulls and 50 sacks cement. Plugging complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS
JAN 23 1981
1-28-81

STATE OF Kansas COUNTY OF Rice CONSERVATION DIVISION
Wichita, Kansas, ss.
R. Darrell Kelso (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 27th day of January, 19 81

My commission expires



Joan Kelso
Notary Public.

STERLING DRILLING COMPANY
 P. O. Box 129
 Sterling, Kansas 67579

WELL LOG ----- STUCKY #1
 Located: C NE NE, Section 13-19S-9W, Harvey County, Kansas

OWNER: Vincent Oil Corporation
 ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: October 3, 1977
 COMPLETED: October 9, 1977

TOTAL DEPTH: 3215'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 135 Clay and Gravel	Ran 8 joints 10 3/4" OD casing, 201' cemented at 212' K.B. with 250 sacks 60/40 Pozmix with 3% cc. Plug down at 1:30 AM, 10-4-77, by Howco.
135 - 215 Blue Sahle	
215 - 722 Shale	
722 - 2540 Shale and Lime	
2540 - 3185 Lime	
3185 - 3215 Mississippi	Ran 86 joints 4 1/2" OD casing, 3241' set at 3214' K.B. Cemented with 125 sacks 50/50 Pozmix, 18% salt, 3/4 of 1% CFR-2. 20 bbl. mud flush ahead. Plug down at 11:00 PM, 10-9-77, by Howco.

RECEIVED
 STATE OIL & GAS COMMISSION
 OCT 12 1977
 VINCENT OIL CO. 17 1980
 CONSERVATION DIVISION
 Wichita, Kansas