


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Harvey County, Sec. 25 Twp. 22 Rge. 3 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SE SE SE  
Lease Owner Drillers Production Co., Inc.  
Lease Name Wall #1 Well No. \_\_\_\_\_  
Office Address \_\_\_\_\_  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 6-18-58 19\_\_\_\_  
Plugging completed 6-20-58 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Red Loyd  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3293 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	283'	none
				5-1/2"	3293'	2856'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked the hole to 3258' and found it open.  
Filled w/sand to 3140' and ran 6 sacks of  
cement. Pulled 5 1/2" casing. Cleared hole  
and mudded to 250', set a rock bridge to 240'  
and ran 10 sacks of cement. Mudded the hole  
to 40', set a rock bridge to 30' and ran 10  
sacks of cement to base of cellar.

7-8-58

STATE CORP. COM.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor West Supply Co., Inc.  
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.  
\_\_\_\_\_  
(employee of owner) or (owner or operator) of the above-described  
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the  
above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 23rd day of June, 19 58

Thomas V. Higgins  
Notary Public.

My commission expires 9-27-58

PLUGGING  
FILE SEC 25 T 22 R 3W  
BOOK PAGE 103 LINE 9

WELL LOG

Company: Drillers Production Co., Inc.  
Farm: Wall

Sec. 25 T. 22 R. 3W  
SE SE SE

Total Depth: 3715  
Comm: Oct. 24, 1951  
Comp: Nov. 27, 1951  
Contractor: Mallard Drlg. Co.

County: Harvey  
Kansas

Casing  
8 5/8" @ 280' w/ 225 sacks cement  
5 1/2" @ 3293' w/ 100 sacks cement

Elevation: 1422 BD  
Production: 839 MCTD

FIGURES INDICATE BOTTOM OF FORMATIONS.

Sand	200	Mississippi	2115
Shale	280	Kinderhook	3518
Shale & Shells	595	Wisener	3541
Shale & Lime	750	Hunton	3545
Lime	800	Maquoketa	3597
Sandy Lime	1090	Dolomite	3635
Shale & Lime	2190	Viola	3656
Lime	2335	Simpson Dolo	3692
Shale & Lime	2435	Simpson Sand	3696
Lime	2930		
Shale & Lime	3145		
Mississippi	3160		
Lime	3298		
Chert & Lime	3385		
Lime	3518		
Shale-Kinderhook	3518		
Lime	3623		
Lime & Shale	3655		
Lime-Viola	3667		
Lime	3694		
Sand	3715 TD		

Clean out to 3258  
Perf 11/s 3150-54  
35/s 3155-67  
1000 gal Acid  
2500 gal Acid  
Workover May 2 to 25, 1958  
Perf 64/s 3210-26  
10,000 Gal Acid Petrofrac  
Swab water - No oil or gas.

**PLUGGING**  
FILE SEC. 25 T. 22 R. 3W  
BOOK PAGE 103 LINE 9

RECEIVED  
STATE GEOLOGICAL SURVEY  
MAY 27 1958  
CONSERVATION DIVISION  
Topeka, Kansas