

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

20228
API NUMBER 15-079-02,228-0000

LEASE NAME Randall

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 25 TWP. 22 RGE. 3W (Eker) (W)

COUNTY Harvey

Date Well Completed

Plugging Commenced 9-17-90

Plugging Completed 9-20-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Harold J. Milburn

ADDRESS 7315 N. Monroe Hutchinson, KS. 67502

PHONE# (316) 663-1616 OPERATORS LICENSE NO. 5526

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, Is well log attached?

Producing Formation Depth to Top Bottom T.D. 3260'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	180'	none
				4 1/2"	3252'	1929'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sanded bottom to 3210' ran 4 sacks cement w/bailer. Shot pipe @2520',
1929'. Pulled to 350' pumped 2 hulls 120 sacks cement, 150 sacks to top.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Harold J. Milburn

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters here in contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524


OCT 1 1990

CONSERVATION DIVISION
SUBSCRIBED AND SWORN to before me this 28 day of Sept., 19 90

Irene Herzberg
Notary Public

My Commission Expires:





Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone (316) 241-1250

McPHERSON, KANSAS 67460

March 28, 1975

COMPANY: HAROLD J. MILBURN
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: RANDALL #1
 LOCATION: S/2 SW/4 NW/4, Section 25-22-3W,
 Harvey County, Kansas
 COMMENCED: March 13, 1975
 COMPLETED: March 27, 1975
 ELEVATION:

0	to	35	Shale
35	to	65	Sand
65	to	400	Shale
400	to	775	Shale & Lime
775	to	1110	Lime & Shale
1110	to	1540	Shale
1540	to	2060	Shale & Lime
2060	to	2400	Lime & Shale
2400	to	2940	Lime
2940	to	3110	Lime & Shale
3110	to	3145	Shale
3145	to	3260	Mississippi
		3260	T. D.

Cut 12 1/2 inch hole to 180' and run 182' of 8 5/8 inch surface casing, cemented with 150 sacks at 180'. Plug down at 2:00 P. M., March 13, 1975. Cut 7 7/8 inch hole to 3260'. Run 3257' of 4 1/2 inch pipe, cemented with 75 sacks of cement at 3252'. Plug down at 6:00 P. M., March 27, 1975.

TOPS: MISSISSIPPI - 3145'

Measurements taken from K. B.


CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your RANDALL #1, located on the S/2 SW/4 NW/4, Section 25-22-3W, Harvey County, Kansas as reflected by the files of Blackstone Drilling, Inc.


 P. E. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 31st day of March, 1975.


 Johnnie L. Schmidt - Notary Public



STATE OF KANSAS
 JUN 23 1977