

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Bear Petroleum, Inc.

ADDRESS Box 438, Haysville, KS 67060

PHONE# (316) 524-1225 OPERATORS LICENSE NO. 4419

Character of Well Good

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-29-94 (date)

by David Wertz (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? No

Producing Formation Mississippi Depth to Top 3168' Bottom 3241' T.D. 3241'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content Surface	From Surface	To	Size	Put In	Pulled out
		Surface	206	8 5/8"	206'	0'
	Production	Surface	3241'	4 1/2"	3241'	510'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set  
Dumped sand to fill from 3241'-3000', dump bailed 4 sax cement, shot pipe off at 510', pulled pipe ran 2" tubing to 260', circulated cement to surface, pulled 2" out of hole, filled hole to surface.

Name of Plugging Contractor Gressel Oil Field Service, Inc. License No. 3009

Address Box 607, Burrton, KS 67060

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Gressel Oil Field Service, Inc.


STATE OF Kansas COUNTY OF Sedgwick, ss.

R.A. Schremmer (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) R.A. Schremmer  
Box 438, Haysville, KS 67060



SWORN TO before me this 7th day of August, 19 94

[Signature]  
 Notary Public

My Commission Expires: April 15, 1995 Debra K. Hill-Johnson

USE ONLY ONE SIDE OF EACH FORM

RECEIVED  
 OIL CORPORATION COMMISSION  
 AUG 1 5 1994  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

VINCENT OIL CORPORATION #1 STRUEBY 23-22-3W  
 230 O. W. GARVEY BLDG. C S/2 SE  
 WICHITA, KS. 67202  
 FLO 193 MCFG/20", AC 750, SIGW, POTENTIAL NOT AVAILABLE

15-079-20388-0000

K. E. S. LIBRARY

VINCENT OIL CORPORATION 24-22-3W  
 230 O. W. GARVEY BLDG. #1 SEEDLE C S/2 NE NW  
 WICHITA, KS. 67202  
 CONTR RED TIGER DRILLING CO. CTY. HARVEY  
 GEOL. BURTON NE EXT (1/8 W)  
 K 1425 KB CM 10/6/80 CARD ISSUED 1/15/81 IP SIGW  
 MISS 3161-3204 OA

LOG	TOPS	DEPTH	DATUM
LANS	2426	-1007	
MISS	3142	-1717	
RTD	3235	-1808	

8 5/8" SET; 4 1/2" 3232/125sx  
 DST (1) 3148-85(MISS)/45-60-90-60,  
 GTS/11" FLO 263MCFG/10" INCR TO  
 283 MCFG/10"/45" (2ND OPEN), FLO  
 283MCFG/90", REG 80'M, SIP 945-  
 935#, FP 52-41/52-41#  
 MICT - GO, PF (MISS) 3196-3204, 3197-98,  
 3188-92, 3169-71, 3161-67, SWB DWN W/SG,  
 AC500G (15%) SWB DWN & FLO 200MCFGPD, CP  
 120#, AC4000G (15% HCL) & 120,000SCF NITRO-  
 GEN, CP 1050#, TP 1020#, FLO EST 1,250  
 MCFGPD THRU 32/64" CK, CP 550#, TP 345#  
 FLO 900-995MCFGPD THRU 18/64" CK, CP 530#  
 TP 430#, SI

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

VINCENT OIL CORPORATION 23-22-3W  
 230 O. W. GARVEY BLDG. #1 STRUEBY C S/2 SE  
 WICHITA, KS. 67202  
 CONTR STERLING DRILLING CTY. HARVEY  
 GEOL. RALPH WHITE FIELD WALL EXT (1/8 W)  
 K 1430 KB CM 11/22/78 CARD ISSUED 3/17/79 IP SIGW  
 MISS 3168-96 OA

LOG	TOPS	DEPTH	DATUM
LANS	2436	-1006	
BKC	2875	-1445	
CHER	3034	-1604	
MISS	3158	-1728	
RTD	3242	-1812	
DBTD	3245	-1815	

8-5/8" 206/90sx, 4 1/2" 3241/100sx  
 DST (1) 3162-3210/30-45-90-60, GTS 4",  
 GA 228 MCFG/30", (2ND OP) GA 168  
 MCFGPD/60", REG 120'M, SIP 1104-  
 1044#, FP 40-91#/60-71#  
 DST (2) 3212-25/45-45-45, 90'OM, SIP  
 745-613#, FP 70-70#/70-80#  
 DST (3) 3230-42/30-45-30-45, 45'M, SIP  
 683-613#, FP 20-30#/30-40#  
 MICT - GO, DD 3243 TO, (MISS OH), TST  
 24,530 CF6PD, DD 3244 TO, TST 24,530  
 CF6PD, NO FL, DD 3245 TO, TST 24,530  
 CF6PD, 8/6 GW, SWB DWN, NSO, AC 300,  
 SWB LD, NSO, TST 115 MCFGPD, SWB WTR  
 W/NSO SET BP @ 3235, PF (MISS) 10/3168-  
 73, 4/3183-85, 4/3186-88, 4/3194-96,

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS