

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION

FORM CP-1

Rev. 03/92

RECEIVED
KANSAS CORP COMM

130 S. Market, Room 2078
Wichita, Kansas 67202

2002 OCT -2 A 11: 58

WELL PLUGGING APPLICATION FORM

(PLEASE TYPE FORM and File ONE Copy)

API #: 15-185-23166-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate sp or completion date

WELL OPERATOR: Mull Drilling Co., Inc. KCC LICENSE # 5144
(owner/company name) (operator's)

ADDRESS: P.O. Box 2758 CITY: Wichita

STATE: Kansas ZIP CODE 67201-2758 CONTACT PHONE: 316-264-6366

LEASE: Steckel Farms WELL#: 1-11 Section 11 Township 22s Range 14w

30' N of E/2 E/2 W/2 Se SPOT LOCATION/QQQQ COUNTY: Stafford

1815 FEET (in exact footage) FROM East LINE OF SECTION (NOT Lease Line)

1350 FEET (in exact footage) FROM South LINE OF SECTION (NOT Lease Line)

Check One: Oil Well _____ Gas Well _____ D&A XX SWD/ENHR WELL _____ Docket # _____
CONDUCTOR CASING SIZE None SET AT NA CEMENTED WITH NA SACKS
SURFACE CASING SIZE 8-5/8" SET AT 361' KB CEMENTED WITH 460 SACKS
PRODUCTION CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:
ELEVATION 1930.9 G.L. 1939.9 K.B. T.D. 3900 PBDT _____ Anhydrite Depth 812
(Stone Corral Formation)

CONDITION OF WELL: GOOD XX POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING:
Plugged well on 09/29/02 in this manner: Heavy mud in hole and between all plugs. Used 175 sx of 60/40 Poz, 6% Gel.
Bottom plug at 3800' with 50 sx, 2nd plug at 870' with 50 sx, 3rd plug at 390' with 50 sx, top plug at 40' with
10 sx cemented to surface. Rathole with 15 sx, no mousehole. Job completed at 9:15 pm on 09/29/02.
Allied Cementing #13153. KCC notified of plugging 09/30/02.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes (YES,NO) IS ACO-1 FILED? ? (YES,NO)
If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
Name: Gary Pugh/Gary Talbott Phone#: (316) 672-9508

Address: P.O. Box 1006 City: Pratt State: Kansas

PLUGGING CONTRACTOR: Sterling Drilling Company KCC LICENSE #: 5142
(company name) (contractor's)

Address: P.O. Box 1006 City: Pratt State: Kansas Zip 67124

PROPOSED DATE AND HOUR OF PLUGGING (If Known): Plugged well at 9:15 am on September 29, 2002.

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY: Operator X Agent _____

DATE: 09/29/02 AUTHORIZED OPERATOR OR AGENT: Gary M. Talbott
(signature) Gary M. Talbott, Agent for Operator

Sterling Drilling Company, Rig #1

Box 1006, Pratt, Kansas 67124-1006
Office Phone (620) 672-9508, Fax 672-9509

SAMPLE LOG

Steckel Farms 1-11

LOCATION: 30' N of E/2 E/2 W/2 Se
API: 15-185-23166-0000

Section 11 T 22s R 14w
Stafford County, Kansas

OWNER: Mull Drilling Co., Inc.
CONTRACTOR: Sterling Drilling Company, Rig #1

COMMENCED: 19-Sep-02
COMPLETED: 29-Sep-02

TOTAL DEPTH: **DRILLER** 3900 FEET
LOGGER 3901 FEET

Ground Elevation: 1931
KB Elevation: 1940

LOG

0 -	9 FEET	Top Sand
9 -	63 FEET	Clay
63 -	94 FEET	Sand and Gravel
94 -	812 FEET	Shales and Clay
812 -	823 FEET	Sand and Redbeds
823 -	845 FEET	Anhydrite (Driller's)
845 -	1760 FEET	Redbeds, Shales and Salt
1760 -	3750 FEET	Limestone, Shale and Dolomite
3750 -	3900 FEET	Arbuckle

CASING RECORDS

Surface Casing-8-5/8"

Spud at 3:15 pm on 09/19/02. Drilled 12-1/4" hole to 361'. Ran 9 joints of 24#, 8-5/8" surface casing, tally 365' set at 361' KB. Cemented with 350sx 60/40 Poz, 3% CC, 2% Gel, Cement did not circulate. Plug down at 9:30 pm on 09/19/02. Tagged cement at 60' and cemented to surface through 1 inch using 110sx 60/40 Poz, 3% CC. Job completed at 1:00 am on 09/20/02 by Allied Cementing. Ticket # 13194. Strapped bottom 2 joints of SP, welded collars on remaining 7 joints.

Production Casing

Plugged well on 09/29/02 in this manner: Heavy mud in hole and between all plugs. Used 175 sx of 60/40 Poz, 6% Gel Bottom plug at 3800' with 50 sx, 2nd plug at 870' with 50 sx, 3rd plug at 390' with 50 sx, top plug at 40' with 10 sx cemented to surface. Rathole with 15 sx, no mousehole. Job completed at 9:15 pm on 09/29/02.

DEVIATION SURVEYS

3/4	degree(s) at	361	feet
Misrun	degree(s) at	3618	feet
3/4	degree(s) at	3644	feet
1	degree(s) at	3794	feet

RECEIVED
KANSAS CORP CO147
2002 OCT -2 A 11: 58