

15-083-20346-0000

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

JAN 4 1974

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum Inc.

Complete Address 306 W. Douglas, Wichita, Kansas Route 2 Great Bend

Lease Name Campbell "Q" Well No. 1

Location C NE SE Sec. 5 Twp. 22 Rge. 23 (E) (W)

County Hodgeman Total Depth 4654'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Damac

Address Great Bend, Kansas License No.

Operation Completed: Hour 2:30Pm Day 28 Month 12 Year 1973

The above well was plugged as follows:

8 5/8" to 480' circulated w/ cement. Mud 4654' to 600'

Spotted 50 sacks cement 600' to 500' Mud 500' to 240'

Spotted 25 sacks cement 240' to 160' Mud 160' to 40'

Plug, Halls [∞] 10 sacks cement 40' to 0'. Sun Cementing Co.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 1/4/74

INV. NO. 8369-W

Signed: [Signature]

Well Plugging Supervisor