

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-079-20320-0000

245 North Water
Wichita, KS 67202

Operator's Full Name Vincent Oil Corporation

Complete Address 230 O. W. Garvey Bldg. Wichita, Ks. 67202

Lease Name Stucky Well No. # 1

Location NE. NE. Sec. 25 Twp. 22-SRge. 3 (~~East~~) (West)

County Harvey Total Depth 3215'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase Ks. 67524 License No. 683

Operation Completed: Hour: 1:30 PM Day: 23 Month: 1 Year: 19 81

The above well was plugged as follows:

10 3/4" sur. csg. 212', 4 1/2" csg. 3214', Perf. 3155' to 60', 3175' to
3184', 3202' to 07', Set bridge at 3150', sand to 3100', 4 sx. cement.
Shot & Pulled 2610' 4 1/2" csg. Left 604' csg. in hole.
Allied Cementing pumped 4 sx. hulls, 13 sx. gel., 50 sx. 50/50 posmix
4% gel, 2 sx. gel., 1 sx. hulls, 50 sx. Posmix 4% gel, down 10 3/4" csg.
Pump Press. 300# S.I.P. 100#

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1-29-81

INV. NO. 8507-E

Signed: Don Thompson
Conservation Division Agent

STATE CORPORATION COMMISSION
Wichita, Kansas
JAN 28 1981
CONSERVATION DIVISION