

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 23 1975

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name O.G. Harper

Complete Address 3409 E. 28th. Hutchinson, Kansas 67501

Lease Name Ediger Well No. # 1

Location C NW SE Sec. 25 Twp. 22 Rge. (E) 3(W)

County Harvey Total Depth 3733'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Art Lamb Casing Plugging Inc.

Address Hutchinson, Kansas License No. # 440

Operation Completed: Hour 5 PM Day 21 Month 10 Year 75

The above well was plugged as follows:

8 5/8"-180'-Circulated w/cement. 5 1/2"-3732'-Cemented. Plug Back-3050'.

Top Perf. 3000'. Sand to 2950'. 5 Sax. Cement.

Mud to 200". Bridge 200' to 200". 25 Sax. Cement at 200'.

Mud top cement to 40". Bridge 40' to 30'. 10 Sax. Cement 30' to 0.

Pulled 2500'- 5 1/2"-Pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed [Signature]
Well Plugging Supervisor

DATE 10/23/75

INV. NO. 9260-E