

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-179-21424-00-00
Spot: SENWSESW Sec/Twnshp/Rge: 19-7S-28W
981 feet from S Section Line, 1852 feet from W Section Line
Lease Name: GAEDE Well #: 1-19
County: SHERIDAN Total Vertical Depth: 4400 feet

Operator License No.: 35245
Op Name: SUEMAUR EXPLORATION & PRODUCT
Address: 539 N. CARANCAHUA SUITE 1100
CORPUS CHRISTI, TX 78401

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	295		270 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/18/2016 12:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: KELLY Company: MURFIN DRILLING CO., INC. Phone: (785) 443-1630

Proposed Plugging Method: Ordered 255 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: NONE
Date/Time Plugging Completed: 12/18/2016 9:45 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st plug @2515 w/50 sx
2nd plug @1695 w/100 sx
3rd plug @345 w/50 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: ALLIED

Plugged through: DP

KCC WICHITA
FEB 14 2017
RECEIVED

INVOICED
FEB 16 2017

District: 04

Signed



(TECHNICIAN)

CM

FEB 02 2017