

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-053-20151-00-00  
Spot: NENESWNE Sec/Twnshp/Rge: 32-17S-9W  
3875 feet from S Section Line, 1503 feet from E Section Line  
Lease Name: NORTHERN NATURAL GAS P Well #: 1-32  
County: ELLSWORTH Total Vertical Depth: 3235 feet

Operator License No.: 3530  
Op Name: VONFELDT, GARY L. DBA KG OIL CO  
Address: 18103 WALTERS LN  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3232		150 SX
SURF	8.625	1359		500 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/06/2017 10:00 AM  
Plug Co. License No.: 33905 Plug Co. Name: ROYAL DRILLING INC  
Proposal Rcvd. from: GARY VONFELDT Company: KG OIL CO. Phone: (785) 483-0610

Proposed Plugging Method: SAND TO 50' ABOVE OH & CAP WITH 10 SX'S CEMENT. PERFORATE AT 1409'. HOLES IN CASING AT 1996'-1550'. RUN TUBING TO 1995' AND PUMP 50 SX'S COMMON CEMENT WITH 3% CC. LET SET 1 HOUR AND TAG. PULL TUBING TO 1409' AND CIRCULATE CEMENT TO SURFACE.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL  
Date/Time Plugging Completed: 02/06/2017 3:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

MIRU, DRILL THRU BRIDGES AND TAG BOTTOM. RAN TOOLS TO LOCATE HOLES IN CASING - FOUND AT 1996' TO 1550'. SAND TO 50' ABOVE OH AND CAP WITH 10 SX'S CEMENT. PERFORATE AT 1409'. RUN TUBING TO 1995' AND PUMPED 50 SX'S COMMON CEMENT WITH 3% CC. PULL TUBING UP TO 1485' AND WAIT 1 HOUR. TAG CEMENT AT 1521'. PULLED TUBING TO 1409' AND PUMPED 185 SX'S CEMENT WITH GOOD CEMENT RETURNS. PULLED TUBING OUT AND TOPPED OFF.

INVOICED

FFR 1

Remarks: DENIED TA WELL. ELI WIRELINE #1514. QUALITY OILWELL CEMENT #3138.

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

14