

1 070300

FEB 10 1987

STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING SECTION  
 200 COLORADO DERBY BUILDING  
 WICHITA, KANSAS 67202

API NUMBER 15- 083-20,639 - 0000

W 2 NW SE, SEC. 19, T 22 S, R 23 W/E

## TECHNICIAN'S PLUGGING REPORT

Operator License # 5042

Lease Name Hays "A" Well # 4

Operator: Edmiston Oil Co., Inc.  
 Name:

County Hodgeman 153.01

Address 1260 KSB Building  
 Wichita, KS 67202

Well Total Depth 4708 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 370

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor Kelson Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1:45 p.m. Day: 10 Month: 2 Year: 19 87

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4707' PBTD 4697' Perfs at 4673-75'

1st plug sand back to 4625' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 150 sx cement.

Plugging Proposal Received by Steve Durrant and Don Ubel  
 (TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 2:45 p.m. Day: 10 Month: 2 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4625' and dumped 4 sx cement on top of sand  
 through bailer,

2nd plug pumped 200 lbs. hulls, 15 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and  
 150 sx cement.

Maximum pressure 600 psi and shut in 200 psi. 2-17-87

Remarks: Recovered 3000' of 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.  
 (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-18-87

DIV. NO. 16145

STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

Signed Dan Gooden  
 (TECHNICIAN)

FORM CP-2/3  
 Rev. 01-84