

1051790

3-17

API NUMBER 15-055-20,093-0060

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C NW SE, SEC. 6, T 22 S, R 33 W
1980 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6234
Operator: Petroleum Production Management, Inc.
Name
Address 209 E. William, Ste. 200
Wichita, KS 67202

Lease Name Stevenson # Well # A 3
County Finney 156.00
Well Total Depth 4800 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 418

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:30 a.m. Day: 17 Month: 3 Year: 19 94

Plugging proposal received from David
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

vers: 5 1/2" at 4796' w/100' sx cement, CIBP at 3927', Perfs at 4740-43, 4747-50'
1st plug CIBP set at 3927' with 5 sx cement on top,
2nd plug pump 80 sx cement at 1100',
3rd plug pump 50 sx cement at 450',
4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 12:20 p.m. Day: 17 Month: 3 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug CIBP set at 3927' with 5 sx cement on top,
2nd plug pumped 80 sx cement at 1100',
3rd plug pumped 50 sx cement at 450',
4th plug pumped 10 sx cement at 40'.

3-22-94

RECEIVED
STATE CORPORATION COMMISSION

MAR 22 1994

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1120' of 5 1/2" casing.
(If additional description is necessary, use BACK of this report.)

INVOICED

I (did / ~~did not~~) observe this plugging.

DATE MAR 29 1994

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 40172