

1050260

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-083-21'144-0000

SE, SEC. 18, T 22 S, R 23 W

660 feet from X/S section line

660 feet from X/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8890

Lease Name Bradshaw Well # 1

Operator: Donald J. Malone, Geol.

County Hodgeman

Name & Address 919 Century Plaza

Well Total Depth 4695 152.59 feet

Wichita, Kansas 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor J-W Drilling, Inc. License Number 5137

Address 200 E. First St. #500, Wichita Kansas 67202

Company to plug at: Hour: 5:00 am Day: 20 Month: June Year: 19 84

Plugging proposal received from Bill Roach

(company name) J-W Drilling Inc. (phone) 316-564-2652

were: to keep hole full of heavy mud and spot plugs through drill pipe.

1st plug at 1620 with 50 sx of cement

2nd plug at 810 with 50 sx of cement

3rd plug at 330 with 50 sx of cement

4th plug at 40 with a solid bridge plug and 10 sx of cement to surface.

5th plug circulate rathole with 15 sx of cement

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8:15 am Day: 20 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1620' with 50 sx of cement, 2nd plug at 810' with 50 sx of cement, 3rd plug at 330' with 50 sx of cement, 4th plug at 40' with a solid bridge and 10 sx to surface. 5th plug circulate rathole with 15 sx of cement.

Remarks: Sun oil well cementing cemented the well using 60/40 pozmix 2% gel 3% c.c. cement (if additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-27-84

INV. NO. 2149

Signed Richard W. Lacey (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION JUN 22 1984 CONSERVATION DIVISION Wichita, Kansas