

1060121

TO: STATE CORPORATION COMMISSION 9-28 API NUMBER 15-083-20,668-0000
SW SW SE SEC. 23, T 22 S, R 22 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2310 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME RUFF WELL # .1

TECHNICIAN'S PLUGGING REPORT COUNTY HODGEMAN 142.81

OPERATOR LICENSE # 31961 WELL TOTAL DEPTH 4394 FEET

OPERATOR: Buried Hills Production Co., Inc. PRODUCTION CSG: SIZE 5 1/2 " FEET 4382

NAME AND ADDRESS 1050 17TH ST, STE 1550 SURFACE CASING: SIZE 8 5/8 " FEET 1326'

ADDRESS DENVER, CO 80265

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR PLAINS INC LICENSE NUMBER 4072

ADDRESS PO BOX 346, NESS CITY, KS 67560-0346

COMPANY TO PLUG AT: HOUR: 11:30 AM DAY: 28 MONTH: 09 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM _____

(COMPANY NAME) PLAINS INC (PHONE) 785-798-3995

WERE: PERFORATED AT OPEN HOLE

RUN TUBING TO PERFS AND SPOT 25 SX CEMENT. PERFORATE AT 1300' AND CIRCULATE CEMENT WITH 325 SX. USE 60/40 POZMIX 6% GEL.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 2:00 PM DAY: 28 MONTH: 09 YEAR: 1998

ACTUAL PLUGGING REPORT _____

1ST PLUG SANDED TO 4325' WITH 5 SX CEMENT. 10-14-98

2ND PLUG AT 1400' WITH 50 SX CEMENT.

3RD PLUG AT 600' WITH 50 SX CEMENT.

4TH PLUG AT 40' WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY HALLIBURTON. RECOVERED 2100' OF 5 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Mike Maier
(TECHNICIAN) FORM CP-2/3

10-15-98
60114
C

RECEIVED
STATE CORPORATION COMMISSION
OCT 15 1998