

To: 1 060058 9-17
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 083-21,079-0060
N/2 SW SW, SEC. 23, T 22 S, R 23 W/E
990 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4058
Operator: American Warrior, Inc.
Name:
Address: P.O. Box 399
Garden City, KS 67846

Lease Name Scothorn Well # 2
County Hodgeman 148.20
Well Total Depth 4560 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address P.O. Box 467, Chase, KS 67524-0209

Company to plug at: Hour: 1:40 p.m. Day: 17 Month: 9 Year: 19 97

Plugging proposal received from Kevin Wiles
(company name) American Warrior, Inc. (phone) 316-275-2963

were: 4 1/2" at 4559', Open hole 4559-4560'
1st plug fill 4 1/2" casing through tubing with cement,

Check backside.

9-24-97

Plugging Proposal Received by Mike Maier
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 17 Month: 9 Year: 19 97

ACTUAL PLUGGING REPORT Couldn't get down below 880'.

1st plug ran tubing to 750', circulated cement to surface with 80 sx,

2nd plug pulled tubing, put swedge on 4 1/2" and pumped 90 sx cement.

Maximum pressure 600 psi and shut in 250 psi.

3rd plug tied onto backside and pumped 35 sx cement, pressured to 400 psi and held, shut in with 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery.

(If additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED

SEP 26 1997

DATE

INV. NO. 49138

Signed Michael Maier
(TECHNICIAN)