

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION 75'E of C E/2 SW SW 19, T 22 S, R 23 W/8  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- - Not available

TECHNICIAN'S PLUGGING REPORT

Operator License # 5042

Lease Name Hays "A" Well # 6

Operator: E. K. Edmiston  
Name & 1260 KSB & T Building  
Address Wichita, KS 67202

County Hodgeman

Well Total Depth 4705 feet 152.91

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour 10:30 am Day: 8 Month: February Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Bob Brenneman

(company name) Kelso (phone) 316-938-2348

were: PBD 4684 Top Perfs 4656 1st plug sanded back to 4600' and dumped

5 sx cement through the bailer. 2nd plug 3 sx hulls, 10 sx gel, 70 sx cement,

15 sx gel, and 1 sack hulls and released 8 5/8" rubber plug and pumped additional

120 sx cement. Max pressure 700# and shut-in pressure 300#

Signed Richard W. Lucas  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:15 pm Day: 8 Month: February Year: 19 84

ACTUAL PLUGGING REPORT PBD 4684 Top Perfs 4656 1st plug sanded back to 4600' and

dumped 5 sx cement through the bailer. 2nd plug 3 sx hulls, 10 sx gel, 70 sx cement,

15 sx gel, and 1 sack hulls and released 8 5/8" rubber plug and pumped additional

120 sx cement. Maximum pressure 700# and shut-in pressure 300#

Remarks: They recovered 2300' production pipe  
Use 60/40 Pozmix 2% gel and 3% cc by Allied

I hereby certify that the above plugging instructions were given as herein stated  
and that I (did / ~~did not~~) observe this plugging.

INVOICED  
DATE 2-14-84  
INV. NO. 0203

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 13 1984  
CONSERVATION DIVISION  
Wichita, Kansas

Signed Richard W. Lucas  
(TECHNICIAN)